

DESIGN  
of  
A Double Leaf Trunnioned Deck Bascule Highway Bridge with  
Cantilever Type Deck Plate Girder Approach Spans.

A THESIS

Submitted for the Degree of

MASTER OF SCIENCE  
IN CIVIL ENGINEERING

By

William C. Mason  
B. S. in Civil Engineering 1925  
GEORGIA SCHOOL OF TECHNOLOGY

- - - - -

This Thesis is Approved by:

Sub-Committee of the Committee  
on Advanced Degrees of the  
Georgia Tech Faculty.

JUNE 1932

## CONTENTS

Pages No.1 to No.5 incl.The Bascule Bridge.

Pages No.6 to No.8 incl.General Description of Project.

Plate No. I Perspective View of Bascule Span

### LIST OF DRAWINGS

Sheet No. D\*1, Longitudinal Elevation of Project.

- " No. D-2, Elevation of Bascule Span.
- " No. D-3, Longitudinal Girder of Bascule Leaf.
- " No. D-4, Floor Beams FBO, FBI, FB2.
- " No. D-5, Operating Machinery.
- " No. D-6, Counterweight Drive Shaft.
- " No. D-7, Trunnion and Indicator Mechanism.
- " No. D-8, Crosssection in Front of Trunnion Girder.
- " No. D-9, Longitudinal Section of Main Bascule Girder.
- " No. D-10, Plan of Pier and Fender Location.
- " No. D-11, Live Load Girder.
- " No. D-12, Detail of Center Lock.
- " No. D-13, Sway Bracing.
- " No. D-14, Bascule Leaf Framing Layout.
- " No. D-15, Approach Deck Section.
- " No. D-16, Approach Span Floor Beams and Girders.
- " No. D-17, Stress Sheet for Approach Spans.

### GENERAL DESIGN

Sheets No. B1 to B36, Design of bascule span structure.

- " No. M1 to M13, Design of bascule machinery.
- " No. A1 to A29, Design of approach spans.

Page No. B1, Bibliography.

32010



## FOREWORD

Most bascule bridges are ugly structures, and with this fact in mind, the writer has endeavored, in this design, to produce a bascule type bridge, having not only stability and economy, but something of grace and beauty also.

The bascule span in this project embodies structural features that the writer has observed on various bascule bridges now in operation. Much difficulty was experienced in obtaining methods of design, since most authors of bridge engineering text-books, after having described and compared various types of bascule and draw bridges, pass over the question of design entirely. Therefore, many of the design problems had to be worked out without recourse to text-books, and, therefore, will perhaps not appear conventional to one who is familiar with the practice of bascule bridge design.

The approach spans are rather unusual in design, and afforded a very interesting problem. Being of the cantilever type, a statically determinate structure was possible, at the same time, making possible the multiple span arch outline which was desired for this structure.

## THE BASCULIN BRIDGE

### EARLY TYPES:

The modern bascule span is a descendant of the medieval drawbridge. It then served a double purpose, bridging the moat when lowered, and barricading the castle doorway when raised. This early drawbridge was not counterweighted to any appreciable extent. It was raised by hand by means of an out-haul line attached to the free end of the span, and passing upward and over a system of pulleys. This early bridge could not be called a bascule, since the word "Bascule" comes from the french, meaning a balance.

Due to the lack of convenient power for operating and the crude and inefficient methods of counterweighting, very little progress was made in bascule bridge development until comparatively recent years. The real beginning of the modern bascule began in the 19th century, and really can be said to have begun not over forty years ago. The Tower Bridge of London, constructed during the year 1894 probably marked the beginning.

### INHERENT ADVANTAGES IN THE BASCULIN BRIDGE:

Rapidity and extent of opening, to permit the passage of vessels and closing again for bridge traffic, has been a great factor in the success and popularity of the modern bascule bridge. For small vessels, the bascule may be raised slightly, thereby interrupting bridge traffic for a proportionally less time than that required for full opening. Too, river traffic can approach to within a very short distance of the bridge while waiting for it to open. Where river traffic is congested, the time saving thus effected is valuable in reducing delay, both to river and bridge traffic.

### MODERN TYPES:

Modern bascules are comprised in three classes -

The trunnion type; The rolling lift type, and The roller bearing type. Any of these may be single or double leaf; through spans or deck spans; trussed or girders. In the trunnioned type, the trunnions are placed near the center of gravity of the entire moving leaf. In the rolling lift type, the center of rotation changes continually throughout the entire period of opening and closing. The center of gravity of the moving leaf travelling backward and forward on a horizontal line. This changes the position of the reaction of the superstructure on the pier throughout the period of opening and closing of the bridge.

In the roller bearing type, the trunnion is eliminated. The center of rotation is coincident with the center of gravity of the moving leaf. The load is carried by means of roller bearings on a curved track. This device allows the stress to be distributed over a greater area, thereby reducing the unit bearing stress, and decreasing the frictional resistance due to rotation.

There are four principle types of bascule bridges in general use at the present time:- The Hall; The Chicago or Simple Trunnion type; The Scherzer; and The Strauss. The Scherzer type lead in the number in operation, the Strauss next; The Hall having the fewest in operation.

#### DESIGN AND REACTION PROBLEMS:

As the name implies, the bascule bridge is a balanced moving span. In order that the operating machinery may be as light as possible, it is essential that the moving leaf be in almost perfect balance. The only loads then on the operating machinery will be, those due to inertia, wind and friction. It is necessary, therefore, that in designing the main girders or trusses, the center of gravity of the entire moving leaf be coincident with the center of rotation.

In double leaf bascules, at the center of the span a

lock called the shear lock is used. The purpose of this lock is to make both leaves of the moving span deflect equally when a greater load is applied to one leaf than to the other. The maximum shear on this lock will occur when one leaf is fully loaded and no load on the other. When the bridge is locked at the center for both moment and shear, the bridge becomes a simple span supported at the live load bearings.

When double leaf spans are designed with a reaction arm or anchor, to resist the overturning force about the live load bearings, due to the live load on the moving leaf, care must be taken in erection to see that the anchor arm does not come in contact too soon. If it does, it causes excessive stresses in the trunnions and their bearings. The anchors should never come in contact until the center of gravity of the combined live and dead loads passes the live load bearings. The anchors furnish a downward reaction, and since the shear lock cannot be counted on for upward reaction (on account of the possibility of full live load on the opposite leaf) the moving leaf, under live load, becomes a beam over-hanging two supports. Before any live load comes on the moving leaf, the center of gravity of the dead load is at the approximate center of trunnion. As the live load moves on to the moving leaf, the center of gravity moves forward toward the live load bearing, and the entire moving leaf is supported at both trunnions and live load or forward bearings, the river arm and counterweight arm overhanging these two supports. As the load continues to move forward, it becomes great enough to balance the entire span, the center of gravity of the combined live and dead loads move to the live load bearings, and the load on the trunnions becomes zero. As the live load increases and continues to move toward the centre of the bridge, the counterweights are over-balanced by the river arm, and the rear anchors

come into play, exerting a negative or downward reaction, and the live load bearings take the total load, both live and dead, and a load equal to the negative reaction of the anchor.

Therefore, care should be taken to see that the anchor is so adjusted that it begins to function at the moment that the centre of gravity of the total live and dead load reaches the live load bearings. With this adjustment undue deflection of the trunnions is eliminated. In order that the operation of seating may be quiet, and chattering eliminated, it is customary to provide oak blocks at the anchors, these being slightly resilient, therefore, compress slightly as the load is applied.

In order to know the correct clearance at which to set the anchor blocks, it is necessary to know:-

- (1) The difference in deflection of the anchor arm when supported at the trunnion, and when supported at the live load bearings.
- (2) The difference in deflection of the trunnion girder at the trunnion supports under no live load on the span and under full live load.
- (3) The ratio of the distance from live load bearing to the center of the anchor bracket, to the distance from the live load shoe to the center of the trunnion.
- (4) The amount of compression induced in the oak blocks from the full live load reaction.

The clearance between the anchor blocks and the anchor block bracket should be; the rise of the anchor due to the difference in deflection of the trunnion girder under no live load and under full live load; less (a) The difference between the deflection of the counterweight arm with support at live load bearing, and with the support at trunnion and (b) The amount by which the oak anchor blocks

compress under full live load uplift on the anchors. If this gives a negative result, the oak anchor blocks would be under some compression before any live load came on.

This would prevent a positive seating of the live load shoes on the live load bearings, and, therefore, would cause a chattering of the span. From this it can be seen that it is advisable to so adjust the anchor blocks that they just touch at the instant that the live load shoes come in contact with their bearings.

Particular care should be taken to see that the trunnion bearings are in correct alignment. Inasmuch as the center line of the trunnions will not be at right angles to the final plane of the trusses until the full dead load is on the span, rivetting should not be performed until the entire steel work is in place. This can be held in place by means of temporary bolts. After the steel work in both leaves has been rivetted, except one panel of laterals, these being in place and bolted only, the two leaves should be lowered and checked for alignment, meeting, deflection, etc. If the two leaves are out of alignment, the panel of bolted laterals may be removed and the leaves aligned by means of diagonal rods with turn buckles. The laterals may then be reamed and rivetted. If there is a difference in level between the two adjacent leaves, this may be corrected by means of shims at the live load bearings.

## GENERAL DESCRIPTION OF PROJECT

The structure considered in this design is a double leaf transition type, bascule highway bridge, with approaches of three spans each, of deck plate girder type.

In the bascule span, there will be two main bascule piers of reinforced concrete, each supporting one bascule leaf and its appurtenant machinery. Each bascule pier also supports one end of the suspended span of the approach.

Each bascule leaf is operated by an electric motor geared to pinions which engage with a rack located at the rear of the counterweight chamber, and in a vertical plane passing through the center line of the moving leaf and parallel to the main longitudinal girders. There is one motor for each leaf, directly connected to the operating machinery. When both moving leaves are lowered for traffic, they are locked at the center of the bridge by means of shear locks. When in the raised position, the roadway is protected by means of electrically operated gates. The operation of the center locks is interlocked with the roadway gates, and the operation of raising the moving leaves is interlocked with the operation of the center locks, making it necessary to lower the gates before the center locks can be drawn, and then to draw the center locks before the moving leaves can be raised.

Both leaves are provided with automatic electric devices to break the electric circuit and to operate electric brakes when the moving leaf is near the end of its travel. A gasoline engine, together with hand brakes is provided for emergency operation. The center locks are operated by means of a small electric motor, direct connected to gears pinions and crank-shaft located under the deck at the center of the bridge. Provision is made for hand operation

in case of emergency.

Each moving leaf will be balanced with a counterweight. These counterweights are of reinforced concrete construction, built up and around a structural steel frame. Each counterweight has within it two chambers for the accommodation of balance blocks to provide for adjustment for variation in weight due to seasonal variation, snow, ice, etc.

The bascule leaves are of the deck girder type. Floor beams are plate girders and stringers of steel I beams. The floor system of the moving leavings will be of creosoted plank with asphalt plank wearing surface.

Each counterweight pit is equipped with a two inch centrifugal sump pump operated by a three H.P. motor to drain off leakage through the walls or from the roadway above.

Approach spans are of the deck plate girder type concrete encased. Each approach consisting of three spans designed in the form of arches. The center span consists of a beam over-hanging the two center piers. On the cantilever ends a span is suspended with a pin connection, the other end of this suspended span being supported on the bascule pier or shore abutment as the case may be.

Approach span decks are of reinforced concrete, supported on steel I beam stringers, which in turn are framed into plate girder floor beams. It should be noted here that in the pin connected panels the stringers are to have flexible connections to the floor beams. All floor beams and stringers are to be encased with concrete, while the main girders are to be wrapped with galvanized steel fabric and grouted.

After erection, all exposed metal parts of the bascule span are to be painted to match the concrete portions of the balance




of the structure, the intention being to produce a bridge having the beauty and grace of a multiple span arch bridge, and at the same time the utility of a bascule lift.

Both bascule piers are protected with fenders. This protection is required by the U. S. War Department on all bridges constructed across navigable rivers of the United States. These fenders are built up of 12 x 12 creosoted waling, bolted to pile dolphins with galvanized bolts. Each dolphin is built up of three pipes, except the dolphins at each intersection of the pier protection and wing fender, which is a seven pile dolphin.

Too much emphasis cannot well be put on the importance of exercising good judgement and experience in the construction of pier fenders. The piles must have sufficient resiliency to give under the impact of shipping, and the waling must be of sufficient strength to transmit the shock of impact to the piling without breaking. It is certainly poor economy to build a pier fender of flimsy construction that may result in an accident to the pier, and may even cause the collapse of the bridge itself. No fender at all is far better than one of light or insufficient construction, for with no fender, care would be exercised to avoid accidents, while the fender of inadequate construction would only create a false sense of security.

## BIBLIOGRAPHY

- 1,-Waddels Bridge Engineering.
- 2,-Mile Ketchums Structural Engr's Handbeek.
- 3,-Willing's Design of Masonry Structures and Foundations.
- 4,-Machinery's Handbeek.
- 5,-American Civil Engineers Handbeek.
- 6,-Heel and Kinne Structural Engineers Handbeek Library.
- 7,-Trustwine Civil Engineers Handbeek.
- 8,-Steel Structures by Merrie.



*Plate #1*

GOVERNING DIMENSIONS

|  |         |
|--|---------|
| Clear Channel at water line                          | 100'-0" |
| Clear Channel at tip of raised leaves (L of opening) | =       |
| Elevation of roadway surface                         | 100.00  |
| Low water level                                      | 76.00   |
| High water level                                     | 86.00   |
| Bottom of existing channel                           | 55.00   |
| " " proposed "                                       | 50.00   |
| Bottom of piers                                      | 50.00   |
| Clear width of roadway between curbs                 | 24.00'  |

LOADS

|           |               |              |
|-----------|---------------|--------------|
| Dead Load | Asphalt Board | 85#/cu. ft.  |
| " "       | Plain timber  | 4#/Bd. ft.   |
| " "       | Creosoted "   | 5#" " "      |
| " "       | Concrete      | 150#/cu. ft. |

LIVE LOADS

2-15 Ton Trucks side by side followed by a uniform load of 80#/b' of bridge floor

2-15 Ton Trucks of following dimensions:-

Distance between axles 10ft., wheel gauge 6'

Two thirds of the load on the rear wheels

Space occupied by Truck 20ft. long by 9ft. wide

IMPACT

In order to provide for the dynamic increment of stress due to the moving loads, the computed Live Load stresses are increased by the following percentages:-

|  |            |
|--|------------|
| Floor stringers                          | 60 percent |
| Intermediate floor beams                 | 50 " "     |
| Stringers & floor bms. at break in floor | 100 " "    |

The maximum live load stresses in the longitudinal girders are increased by a percentage obtained by the formula  $P(\text{percentage}) = \frac{100}{2.6L + 300}$ , where  $L$  = the loaded length of bridge, in feet, producing the max. stress in the member. When the bridge is open or in motion, the dead load stresses are increased by a flat 20 per cent to provide for vibration effects.



IMPACT AT ANCHORAGE

The computed uplift stresses in the anchorage at heel of anchor arm are to be increased by 40 per cent

WIND LOAD

When in the closed position the bridge is designed for a lateral load of  $30 \frac{\text{lb}}{\text{ft}^2}$  of exposed surface

When in the open position a wind force of  $15 \frac{\text{lb}}{\text{ft}^2}$  is considered as acting in any direction. The stresses caused by the above specified lateral forces are not increased for impact by any percentage such as given by the formula given in the previous paragraph

For stresses produced by longitudinal or lateral wind forces combined with those from live load, dead load and impact stresses, the allowed unit stresses may be increased 25 percent over those given in the table of allowed stresses, but the section shall not be less than would be required if the wind forces were neglected and the 25 per cent increase not allowed.

SHEAR AT CENTER OF BRIDGE

The amount of shear transferred from one leaf to the other through the centre lock is assumed to be the amount given by the following formula:-

$$S = \frac{P(A)^2}{4(L)} \left( 3 - \frac{A}{L} \right)$$

Where  $S$  = Shear carried by centre lock

$P$  = any concentrated load

$A$  = distance of  $P$  from Live Load girder shoe

$L$  = length of forward arm (centre of bridge to live load girder)

PERMISSIBLE STRESSES

The size and make-up of each member shall be proportioned for stresses due to the following loads, and combinations of loads:-

- (1) Dead load only
- (2) Dead load, live load and impact
- (3) Dead load, live load and impact, together with wind loadings. For these various load combinations, the permissible unit stresses in the following table shall not be exceeded

| Kind of Stress   | Permissible Stress for Combined loads, dead, live, and impact (lb per sq. inch) | Permissible Stress for Dead Load Only (lb per sq. inch) |
|--|---|---|
| Steel reinforcement in tension   | 18000   | 14000   |
| Steel in compression, 15 times stress in surrounding concrete                                      |   |   |
| Steel in Shear   | 12000   | 9000  |
| Concrete in tension  | 0   | 0   |
| Concrete in compression due to bending   | 650   | 500   |
| Concrete in bearing  | 400   | 300   |
| Concrete in shear (no web reinforcing)   | 40  | 30  |
| Concrete in shear (diagonal tension) beams having shear reinforcement of bent-up bars and stirrups | 120   | 90  |
| Bond of concrete & deformed bars   | 100   | 70  |

Counterweights - The counterweights shall be so designed that they will balance the moving part in all positions and so fashioned that they can be easily and properly adjusted for variation in weight by adding or removing definitely located weights. They shall be of concrete construction, built on and around a structural frame thoroughly reinforced and hooped, or else encased in steel boxes.

Anchor Arm Lateral System. The lateral bracing will be designed to extend to the trunnions as well as to the anchorage at the heel of the counterweight and will be proportioned to carry the full load to either point.

Buffer Blocks Both the anchor buffer blocks and the blocks for stopping the bridge in the open position are to be made of sound, well-seasoned white oak, entirely free from knots or other imperfections.


Other details of design and fabrication are according to the ordinary rules for such work as found in the various specifications for the design and fabrication of steel bridges.



| Kind of stress   | Permissible stress for combined loads, dead, live and impact (lb. per sq. inch) | Permissible stress for Dead Load only (lb. per sq. inch) |
|--|---|--|
| Axial and bending tension on net section of structural steel                                       | 16000   | 12000  |
| Upset bars and rods where not annealed   | 12000   | 9000   |
| Axial compression on gross section <sup>+</sup> :-<br>(L = unsupported length of member in inches) | $16000 - 70 \frac{L}{r}$  | $12000 - 50 \frac{L}{r}$                                 |
| Direct compression on:-  |   |  |
| Cast-steel bearing and struct. steel plates  | 16000   | 12000  |
| Cast-iron blocks   | 14000   | 10000  |
| Bending on:-   |   |  |
| Extreme fibre of pins  | 24000   | 18000  |
| Shearing on:-  |   |  |
| Rivets and turned bolts in floor connections, shop and field                                       | 8000  | 6000   |
| Pins and shop rivets, except in floor conn.  | 12000   | 10000  |
| Turned bolts and field rivets except in floor connections  | 10000   | 8000   |
| Web of girders, net section  | 12000   | 10000  |
| Web of girders, gross section  | 10000   | 8000   |
| Bearing on:-   |   |  |
| Rivets and turned bolts in floor connections, shop and field                                       | 16000   | 12000  |
| Pins and shop rivets, except in floor conn.  | 24000   | 20000  |
| Turned bolts and field rivets, except in floor connections   | 20000   | 16000  |
| Expansion rollers, per lin. inch<br>(d = diameter of the roller in inches)                         | 500d  | 500d   |


<sup>+</sup>,  $\frac{L}{r}$  shall not exceed 100 for main members nor 120 for subordinate members

Allowable Static Pressure on Masonry  
Unreinforced mass concrete may be loaded as follows  
1:2½:5 Concrete not more than 500 #/sq. ft.  
1:2:4 Concrete not more than 650 #/sq. ft.



TRANSVERSE SECTION  
THRU. APPROACH DECKS











# GENERAL DESIGN

Sheet #B5

## Stringers and Floor Beams

Stringers 15 ft. span

Spaced @ 2.42' o.p.

Dead Loads  $1\frac{1}{2}"$  asphalt board  $\frac{1.5}{12} \times 85 = 10.65$   
" " 4" creosoted pine flooring = 20.00  
" " wt. of stringer  $\frac{30.65}{40.00}$

Total dead load per ft. of stringer  $30.65 \times 2.42 = 74.40$   
say 115 #/ft.

Dead Load Mom.  $\frac{115 \times 15 \times 15}{8} = 2590$  ft.# Shears 1020  
L.L. "  $= \frac{10000 \times 15}{4} = 37600$  ft.# 5000

Impact 60% of 37600 = 22600 ft.# 3000  
62790 ft.# 9020

Section Modulus Req'd.  $\frac{62790 \times 12}{16000} = 47.2$

A 12" I @ 45# will be adopted.

## Floor Bm

F.B.3

$$\frac{5000 \times 5.16}{15.16} = R_1, 1700$$

$$R_1 = 1700 + 10000 = 11700 \#$$

Dead Loads

$$1\frac{1}{2}" \text{ asphalt} = 1 \times 15.16 \times 10.65 = 162$$

$$\text{Flooring} = 1 \times 15.16 \times 20 = 304$$

$$\text{Stringers} = 15.16 \times 45 \times \frac{1.2}{29.5} = 278$$

$$\text{Floor Bm. 3} = 135$$

$$\text{Total dead load} = 879 \#/\text{ft.}$$

See diagram on next sheet

$$M_d = M_a = 35000(5.165) - 879\left(\frac{5.165}{2}\right)5$$
$$= 182000 - 11350 = 170650$$


$$M_b = 35000 \cdot 11.165 - 11700(6) - 11.165(879)\left(\frac{11.165}{2}\right)$$
$$= 392000 - 70200 - 54600 = 267200 \text{ ft. \#}$$


Shears Lt. of pt. 'a'  $= 35000 - (879 \cdot 5.165) = 30460 \#$

Rt. " " a  $= 30460 - 11700 = 18760 \#$

Lt. " " b  $= 18760 - (879 \times 6) = 13486 \#$

Rt.





Web req'd. at 10000  $\#$  =  $\frac{47000}{10000} = 4.7^\circ$   
 Web used =  $19.88^\circ$  Gr.  
 Eff. depth 4'-5 1/4"  
 Flange stress =  $4.25'$   
 Section Req'd. (net) =  $67400 \text{ \#}$   
 8 Web =  $4.23^\circ$  net  

|                    | Gr   | Gr    | Net  |
|--------------------|------|-------|------|
| Top Flange         | 2.48 | 2.48  | 2.48 |
| 2LS 4x4x 7/16      | 6.62 |       |      |
| Bott. Flange       |      | 7.94  | 7.06 |
| 2LS 6x3 1/2 x 7/16 |      |       |      |
| Total              | 9.10 | 10.42 | 9.54 |

Floor Bms FB1 & FB2

Shears & MOMs. same as in FB3

$$\text{Web req'd.} = \frac{47000}{10000}$$

Web used  $31 \times \frac{3}{8}$ "

Eff. Depth

Flange Stress

Sect. Req'd. (Net)

$\frac{1}{8}$  Web

Top Flange  $2L54 \times 4 \times \frac{5}{8}$ "

Bot. "  $2L36 \times 4 \times \frac{1}{2}$ "

Total

$$= 4.70$$

$$= 11.62^\circ \text{ Gr.}$$

$$2.42 \text{ ft.}$$

$$119000 \#$$

$$7.42^\circ \text{ net}$$

| Gr.   | Gr.   | Net  |
|-------|-------|------|
| 1.45  | 1.45  | 1.45 |
| 9.22  |       |      |
|       | 9.50  | 8.50 |
| 10.67 | 10.95 | 9.95 |

Floor Bm. FB0.

$$\text{D.L. Mom.} = 72000 \div 2$$

L.L. Mom.

100% Impact

Total Moment

$$\text{D.L. Shear } 11600 \div 2$$

L.L. "

100% Impact

$$= 36000 \text{ ft.}$$

$$= 190,900 "$$

$$= 190,900 "$$

$$417800 "$$

$$= 5800 \#$$

$$= 23400 \#$$

$$= 23400 \#$$

$$= 62600 \#$$

Shear Transferred from one leaf to the other through centre lock

$$S = \frac{P(A)^2(3 - \frac{A}{L})}{4} = \frac{20000(60.3)^2(3-1)}{4(60.3)} = 10000^\circ = 10000 \#$$

Total Shear

$$\text{Web Req'd.} = 72600 \div 10000$$

Web Used  $= 27 \times \frac{3}{8}$ "

Eff. Depth  $= 2.08 \text{ ft.}$

Flange stress

Sect. Req'd. Net

$$= 72600 \#$$

$$= 7.26^\circ \text{ Gr.}$$

$$= 10.125^\circ$$

$$= 2.08 \text{ ft.}$$

$$= 205,000 \#$$

$$= 12.55^\circ$$


$\frac{1}{8}$  Web

Top Flange  $2L56 \times 6 \times \frac{13}{16}$


Bot. "  $2L56 \times 6 \times \frac{13}{16}$

Total

| Gr.   | Gr.   | Net   |
|-------|-------|-------|
| 1.27  | 1.27  | 1.27  |
| 18.18 |       |       |
|       | 18.18 | 17.18 |
| 19.45 | 19.45 | 18.45 |




FLOOR BEAM FBO




FLOOR BMS. FB1 & FB2

*Symetrical Abt. 2*




PLAN




ELEV. OF MAIN GIRDER





PLAN OF PIER & FENDER LOCATION





Wts. of F.B.O

Dead loads Asphalt  $18.75 \times 13 = 244$

4" Pine flooring @ 5#/bd. ft.  $5 \times 4 \times 13 = 260$

Stringers  $5.5 \times 40 = 220$

Connections  $= 40$

Total  $= 764$

FBO  $226 \times 13.2 \div 7.6 = 391$

Handrail  $= 100$

Bascule Girder  $= 300$

1555

FBO Total Dead load  $1555 \times 7.5 = 11663$

FB1  $= 764$

$391 + 100 + 245 = 736$

1500

FB1 Total D.L  $1500 \times 15 = 22500$

FB2 Same as FB1  $= 22500$

FB3  $= 23000$

FB4  $= 764$

$100 + 380 + 265 = 745$

1509

$1509 \times 12 = 18108$

$\frac{11700(70) + 22500(54.875) + 22500(39.75) + 23000(24.625)}{13.12} +$

$\frac{18000(9)}{13.12} = P_{wt.}$

$\frac{819000 + 1,230,000 + 894000 + 567000 + 162000}{13.12} = P_{cw}$

$= \frac{3672000}{13.12} = 280000\#$

$\therefore$  Weight of counterweight and supporting frames  $= 280000\#$

# Weight of Counterweight Frames

2 Frames Thus

Girders  $\#$  79x13 = 1027

4 Ls = 79

2 Fls = 39


Connections = 18

1163

$2 \times 1163 \times 13 = 30280 \#$

Volume of steel =  $\frac{30280}{495} = 61.8$

$62 \times 150 = 9300 \#$  equiv. weight of concrete displaced by steel.



Approx. Typical Counterweight Section

## Design of counterweight

Volume of prism  $10.92 \times 26.33 \times 16.25 = 4673 \text{ cu ft}$

Volumes to be deducted

less = 1285

$2(4.25 \times 3.25 \times 6.33) = 175$

$(3.58 \times 8.33 \times 26.33) \div 2 = 392$

$(6 \times .83 \times 26.33) \div 2 = 66$

$(4.2 \times 2.58 \times 26.33) \div 2 = 14$

$6 \times 15.83 \times .83 \times 1.5 = 118$

$3.58 \times 2.08 \times 26.33 = 196$

$(11.33 \times 2.08 \times 26.33) \div 2 = 324$

1285

$3388 \times 150 = 510000$

## Center of gravity

Areas (A)  $11.83 \times 8.83 = 104.5$

B.  $(8.33 \times 3.58) \div 2 = 14.9$

C.  $(11.83 \times 2.08) \div 2 = 12.3$

D.  $(6 \times .83) \div 2 = 2.5$

Center of gravity of Counterweight Ctd.

E.  $2.33 \times .83 = 2$

F.  $(.83 \times 2.6) \div 2 = 1$

Total Areas = 137.20'

Area Moments.

A.  $104.5 \times 9.49 = 990.00$

B.  $14.9 \times 2.5 = 37.25$

C.  $12.3 \times 11.3 = 138.99$

D.  $2.5 \times 15.7 = 39.25$

E.  $2 \times 15.8 = 31.60$

F.  $1 \times 16 = 16.00$

1253.09

$\frac{1253.09}{137.2} = 9.12'$

See Sketch

Due to seasonal variation counterweight balance blocks will be provided to the extent of approx. 2 1/2 per cent of the entire weight of counterweight


Volume of counter weight chambers =

$4.25 \times 6.33 \times 3.25 = 87.5$  cu. ft. each (2 Thus)


$87.5 \times 150 = 13110 \#$

Using blocks equiv. to one cu. ft. eq.

$88 \times 2 = 176$  Blocks req'd. for each counterweight



## Design of Main Bascule Girders



2-15 Ton Trucks side by side followed by uniform load of 80#/ft.

20000# for rear wheels per girder  
 10000# for front wheels per girder  
 $80 \times 13 = 1040 \#$  per ft. of girder  
 $1040 \times 15.125 = 15750 \#$  per panel

|             |           |   |        |
|-------------|-----------|---|--------|
| L.L. Shears | FBO - FB1 | = | 30000# |
| L.L. "      | FB1 - FB2 | = | 45750# |
| L.L. "      | FB2 - FB3 | = | 61500# |
| L.L. "      | FB3 - FB4 | = | 77250# |

## L.L. Moments

$$20000 \times 60.5 + 10000 \times 50.5 + 15750 \times 37.812 + 15750 \times 22.687 + 15750 \times 7.562 = 1,210,000 + 505,000 + 596,000 + 358,000 + 119,200 = 2,788,200 \text{ ft. \#} = \text{Max L.L. Mom.}$$

$$\text{L.L. Mom. at FB1} = 20000 \times 15.125 + 10000 \times 5.125 = 353,000 \text{ ft. \#}$$

$$\text{L.L. " " FB2} = 20000 \times 30.25 + 10000 \times 20.25 + 15750 \times 7.56 = 926,500 \text{ ft. \#}$$

$$\text{L.L. Mom. at FB3} = 20000 \times 45.375 + 10000 \times 35.375 + 15750 \times 22.687 + 15750 \times 7.56 = 1,732,375 \text{ ft. \#}$$

## L.L. Mom. at front

$$\text{Counterweight frame } 36000 \times 8.25 = 297,000 \text{ ft. \#}$$

$$\text{D.L. Moms. \& Trunnion } 11700 \times 70 + 22500 \times 54.875 + 22500 \times 39.75 + 23000 \times 24.125 + 18000 \times 9 = 3,650,000 \text{ ft. \#}$$

$$\text{D.L. Mom. F.B.1 } 11700 \times 15.125 = 172,000 \text{ ft. \#}$$

$$\text{D.L. " F.B.2 } 11700 \times 30.25 + 22500 \times 15.125 = 694,000 \text{ ft. \#}$$

$$\text{D.L. " F.B.3 } 11700 \times 45.375 + 22500 \times 30.25 + 22500 \times 15.125 = 1,550,000 \text{ ft. \#}$$

D.L. Mom. F.B.4  $11700 \times 60.5 + 22500 \times 45.375 +$

$22500 \times 30.25 + 23000 \times 15.125 = 2,636,000 \text{ ft}$

D.L. Mom. Rear of Cut. frame  $4 \times 280000$

$= 1,120,000$

Pivoting Dead Loads at FB4

D.L. Mom. at FB4

$= +2636000 \text{ ft}$

L.L. " " FB4

$= +2788000$

Total " " FB4

$= +5424000$

$RA = \frac{5,424,000 - 280000 \times 28.12 - 13600 \times 9}{26} = 99300 \text{ #}$

Anchorage Reactions

Fulcrum at FB4 = L.L. bearing

$+L.L. 20000 \cdot 56.36 + 10000 \cdot 46.36 + 7560 \cdot 45.3 +$   
 $14500 \cdot 30.8 + 14500 \cdot 15.1 = 2,600,600$

$+D.L. 11700 \cdot 61 + 22500 \cdot 45.3 + 22500 \cdot 30.18 +$   
 $22500 \cdot 15.09$

$= 2,752,000$   
 $+ 5,352,600$

-D.L & -L.L

$-10000 \cdot 9 - 280000 \cdot 22.12$

$= -6,290,000$   
 $+ 937,400$

$937400 \div 26 = 36000 = \text{Shear at rear Ct. Wt. Frame}$

$937400 \div 17.75 - 36000 = 16800 \text{ " front " " "}$

See tabulation of stresses in longitudinal girders for design of main girders.

Design of splices in longitudinal Girders

Pt. 2

Dist. back to back of flange  $L_s = 60\frac{1}{4}"$

Clear dist. between vert. legs  $= 60\frac{1}{4}" - 6\frac{1}{8}" - 6\frac{1}{8}" = 48"$

Allowing  $\frac{1}{8}"$  at top & bott. of splice plates leaves  $47\frac{1}{4}"$  as hgt. of splice plates

Area of web  $= 60 \times \frac{1}{2} = 30 \text{ sq. inches}$

$30 \times .75 = 22.5 \text{ " } \therefore 22.5 \div 47.75 = .47 = \frac{1}{2}"$

Assume rivets @ 3" spacing  $K = 9600 = \text{shear value of } \frac{3}{8}" \text{ rivet, } r_0 = 21"$

$M_r = \frac{K}{r_0} \sum r^2, M_r = \frac{9600}{21} \times (3^2 + 6^2 + 9^2 + 12^2 + 15^2 + 18^2 + 21^2)$

Resisting Mom. of rivets  $= M_r = \frac{9600}{21} \times 10080 = 4,930,000$



Splice between Pt. 3 &amp; Pt. 4

Distance back to back of flange Ls = 97 $\frac{1}{2}$ "Clear distance between vertical Legs = 97 $\frac{1}{2}$  - 12 $\frac{1}{2}$  = 85"Allowing  $\frac{1}{8}$ " at top and bott. of splice R's. leaves 84 $\frac{3}{4}$ "Area of web = 97  $\times$   $\frac{9}{16}$  = 54.6"54.6  $\times$  .75 = 41"  $\therefore$  41  $\div$  84.75 = .484 =  $\frac{1}{2}$ "Spacing rivets 2 $\frac{1}{4}$ "

$$M_r = \frac{9600}{29.25} \times [8(4.5^2 + 9^2 + 13.5^2 + 16^2 + 18.25^2 +$$

$$16(20.5^2 + 22.75^2 + 25^2 + 27.5^2 + 29.25^2)]$$

$$M_r = 328[8(20.3 + 81 + 182.5 + 256 + 333) + 16(425 + 518 + 625 + 755 + 858)]$$

$$M_r = 328[(872.8)8 + 16(3181)] = 328(6980.4 + 50896) = 328 \times 57876 = 18983000 \text{ in.} \#$$

Pitch of flange rivets, max vert. shear = 453000 #

Value of rivet = 9600 #

Eff. depth = 107 inches

$$\frac{9600 \times 107.75}{453000} = 2.28 = 2\frac{1}{4}"$$

Trunnion Girder

See sketch on next sheet

Dead loads of deck

$$17 \times 4.75 \times 11 = 888$$

$$17 \times 4.75 \times 100 = 8075$$

$$17 \times 55 = 935$$

$$9898$$

$$\text{Unif. L.L. } 5 \times 4.75 \times 80 = 1900$$

$$11798$$

$$\text{Concentrated L.L. } 15000$$

$$26798$$

Reaction for side stringers

$$= 11798 \div 2 = 5899$$


$$+ = 15000$$

$$20899$$


$$V_a = 74495 - 20899 = 53596$$

$$V_b = 53596 - 26798 = 26798$$

$$R_1 = R_2 = 20899 + 26798 + 26798 = 74495$$



Moms.  $A = 74495 \times 4.75 \times 12 = 4,246,215 \text{ in}^3$   
 "  $B = (74495 \times 9.5 - 26798 \times 4.75) \times 12 = 6,964,944 \text{ in}^3$



Assumed wt. of girder  
 2 webs  $2 \times 7 \times 25 \times 15.3 = 5355$   
 4 Cov. Pls.  $\frac{5}{8} \times 4 \times 3 \times 25 \times 25.5 = 7650$   
 8 Ls  $4 \times 4 \times \frac{5}{8} \times 8 \times 15.7 \times 25 = 3140$   
 32 Ls  $3 \times 3 \times \frac{3}{4} \times 32 \times 15.7 = 1632$   
 17777

$17777 \div 23.75 = 750$   
 $4.75 \times 750 = 3560$

Moms.  $A = 8900 \times 4.75 \times 12 = 508000 \text{ in}^3$   
 "  $B = 8900 \times 9.50 - 3560 \times 4.75 = 676000$   
 $V_A = 8900 - 3560 = 5340$   
 $V_B = 5340 - 3560 = 1780$

L.L. + D.L. Impact  
 $M_A = 4,754,000$   
 $M_B = 7,641,000$



Trunnion Girder Ctd.

Sheet # B16

Total Shears

$$\begin{aligned}
 A + \text{support} &= 83395 + 25018 &= 108400 \\
 V_A &= 58936 + 17680 &= 76616 \\
 V_B &= 28578 + 8573 &= 37151
 \end{aligned}$$

$$\begin{aligned}
 \text{Web Req'd. } 108400 \div 10000 &= 10.84^\circ \text{ Gr.} \\
 \text{Web Used } 78 \times \frac{3}{8} &= 29.3^\circ \text{ Gr.} = 27.3^\circ \text{ net} \\
 \text{Eff. Depth} = 6'6'' - 3'' &= 6'3'' = 6.25' \\
 \text{Flange Stress} = 9,933,000 \div 7.25 &= 1,365,000^\circ \text{ at B} \\
 \text{" " } = 6,180,000 \div &= 990,000^\circ \text{ at A} \\
 \text{Flange Req'd.} = 1,365,000 \div 16000 &= 85.5^\circ \text{ Net} \\
 \text{Flange Used } 2 - \frac{7}{8} \text{ I's} &= 63.00 \\
 4 \text{ L's } 4 \times 4 \times \frac{3}{4} &= 21.76 \\
 \text{Web} = 29.3 \div 8 &= 3.67
 \end{aligned}$$

$$87.43 \text{ Gr.} = 85.43^\circ \text{ net}$$

$$\begin{aligned}
 &\text{Spacing of flange rivets} \\
 \text{End to pt. A } \frac{10830 \times 75}{108400} &= 7\frac{1}{2}'' \text{ Bot. fl.} \\
 \text{Pt. A to Centre } \frac{10830 \times 75}{76616} &= 10.6'' \text{ " " } \left. \vphantom{\frac{10830 \times 75}{76616}} \right\} \text{Space Rivet } 6''
 \end{aligned}$$

Place 8 stiffeners under each stringer  
Stiffeners at end

$$\begin{aligned}
 \frac{108400}{14000} &= 7.7^\circ \text{ use } 2 - 3 \times 3 \times \frac{3}{8} \text{ with diaphragm} \\
 \text{Stiffeners at A} \\
 \frac{30358}{14000} &= 2.17^\circ \text{ use } 2 - 3 \times 3 \times \frac{3}{8}
 \end{aligned}$$

See Drwg. on next sheet

End Diaphragms Max. load. 350000#

$$\text{Bearing area req'd.} = 21.9^\circ$$

Use PL 18" x 1 1/2"


Intermediate Diaphragms Max. load 250000#

$$\text{Bearing area req'd.} = 15.65^\circ$$

Use PL 10" x 1 3/4"

For further details see drwgs.

Transformer House





CROSS SECTION IN FRONT OF  
TRUNNION GIRDER

# LONGITUDINAL GIRDERS

| PANEL POINT                        | REAR CT. WT. FRAME                      | FRONT CT. WT. FRAME                     | 2 TRUNNION                               | (1) L. BEARING                           | 3                                     | 2                                       | 1                                     | 0                                       |
|------------------------------------|---|---|--|--|---------------------------------------|---|---------------------------------------|---|
| Shear                              |   |   |  |  |                                       |   |                                       |   |
| D.L.                               | 135000                                  | 280000                                  | 280000                                   | 97600                                    | 79000                                 | 56600                                   | 34100                                 | 11600                                   |
| L.L.                               | 36000                                   | 17000                                   | 68000                                    | 280000                                   | 61500                                 | 45750                                   | 30000                                 | 20000                                   |
| I                                  | 36000                                   | 17000                                   | 68000                                    | 75520                                    | 28100                                 | 20470                                   | 12820                                 | 6320                                    |
| Total                              | 207000                                  | 314000                                  | 416000                                   | 453120                                   | 168600                                | 122820                                  | 76920                                 | 37920                                   |
| Shear in Flgs.                     |   |   |  |  |                                       |   |                                       |   |
| " " Web                            | 207000                                  | 314000                                  | 416000                                   | 453120                                   | 168600                                | 122820                                  | 76920                                 | 37920                                   |
| Sect. Req'd. <sup>100000</sup> Gr. | 20.7° Gr.                               | 31.4° Gr.                               | 41.6° Gr.                                | 45.31° Gr.                               | 16.86° Gr.                            | 12.28° Gr.                              | 7.69° Gr.                             | 3.8° Gr.                                |
| Web used                           | 65x <sup>3</sup> / <sub>16</sub> = 36.6 | 95x <sup>3</sup> / <sub>16</sub> = 53.4 | 119x <sup>3</sup> / <sub>16</sub> = 67.0 | 114x <sup>3</sup> / <sub>16</sub> = 64.2 | 80x <sup>3</sup> / <sub>2</sub> = 40° | 60x <sup>3</sup> / <sub>8</sub> = 22.5° | 48x <sup>3</sup> / <sub>8</sub> = 18° | 43x <sup>3</sup> / <sub>8</sub> = 16.3° |
| Moment                             |   |   |  |  |                                       |   |                                       |   |
| D.L.                               |   | 1,120,000                               | 3,650,000                                | 2,600,000                                | 1,550,000                             | 694,000                                 | 172,000                               | 0                                       |
| L.L.                               |   | 297,000                                 | 612,000                                  | 2,752,000                                | 1,732,375                             | 926,500                                 | 353,000                               | 0                                       |
| I                                  |   | 297,000                                 | 612,000                                  | 1,050,000                                | 656,475                               | 324,000                                 | 105,000                               | 0                                       |
| Total                              |   | 1,714,000                               | 4,874,000                                | 6,402,000                                | 3,938,850                             | 1,944,500                               | 630,000                               | 0                                       |
| Eff. Depth                         |   | 7.7                                     | 9.9                                      | 9.5                                      | 6.6                                   | 4.9                                     | 3.8                                   | 3.7                                     |
| Top Flg. Stress                    |   | 233260                                  | 483000                                   | 674000                                   | 596000                                | 598000                                  | 166000                                |   |
| Bot. " "                           |   | 223000                                  | 483000                                   | 684000                                   | 604940                                | 601588                                  | 166000                                |   |
| Flange Req'd.                      |   | Gr. 14.55                               | Gr. 30.2                                 | Gr. 42.1                                 | Gr. 37.3                              | Gr. 37.3                                | Gr. 10.4                              | Gr. 10.4                                |
| Section Used                       |   | Net 14.55                               | Net 30.2                                 | Net 42.1                                 | Net 37.3                              | Net 37.3                                | Net 10.4                              | Net 10.4                                |
| "B Web                             |   |   |  |  |                                       |   |                                       |   |
| 2x6x6x34"                          |   | 16.88 13.88                             | 16.88 13.88                              | 16.88 13.88                              | 16.88 13.88                           | 16.88 13.88                             | 16.88 13.88                           | 16.88 13.88                             |
| 1 R                                |   | 6.50 5.50                               | 6.50 5.50                                | 6.50 5.50                                | 6.50 5.50                             | 6.50 5.50                               | 6.50 5.50                             | 6.50 5.50                               |
| 1 R                                |   |   | 6.50 5.50                                | 6.50 5.50                                | 6.50 5.50                             | 6.50 5.50                               |                                       |   |
| 1 R                                |   |   | 6.50 5.50                                | 6.50 5.50                                | 6.50 5.50                             | 6.50 5.50                               |                                       |   |
| Total                              |   | 23.38 19.38                             | 44.76 38.76                              | 44.40 38.40                              | 41.38 35.38                           | 39.19 33.19                             | 25.63 21.63                           | 25.41 21.4                              |

Sheet # B17




MAIN LONGITUDINAL GIRDER











OUTSIDE ELEVATION-LONGITUDINAL GIRDER






Sheet D-9



LONGITUDINAL SECTION AT MAIN RASCH RIBBED

## FIXED PORTION



Concentrated load 10000<sup>#</sup> = one rear wheel

Span c-c = 4.75'

Clear span = 4.25'

Dead Loads

Asphalt Board = 11<sup>#</sup>

Slab = 100<sup>#</sup>

Total 111<sup>#/ft</sup>

D.L. Mom. =  $111 \times 4.75^2 \times 1.5 = 3770$

$\frac{10000}{3.33 \times 3.33} = 900<sup>#/ft</sup>$

L.L. Mom. =  $900 \times 4.75^2 \times 1.5 = 30400$

Impact @ 30% = 3040

Total Mom. = 37210

$bd^2 = \frac{M}{K}$ ,  $d = \sqrt{\frac{37210}{12 \times 126}} = \sqrt{24.6} = 4.96"$

Make  $d' = 7"$

Slab D.L. 4.75 × 111 = 530<sup>#/ft</sup> of stringer

Stringer

50  
580

Referring to Sect. "B" on next sheet

D.L. Mom. =  $580 \times 11.25 \times 9.75 - \frac{580 \times 9.75^2}{2} = 35900$

L.L. Mom. =  $8710 \times 12.75 - 5000 \times 9.5 = 63500$

Impact = 19100

Total Mom. = 118500



|       | Moment      | Shear   |
|-------|-------------|---------|
| D.L.  | 35900       | 7530    |
| L.L.  | 63500       | 13000   |
| I     | 19100       | 3900    |
| Total | 118500 ft.# | 24430 # |

$$Sect. Mod = \frac{118500 \times 12}{16000} = 88.8$$

Use 18" I @ 60 #

Overhang 10000 x .5

= 50000 ft.#. L.L.M.

D.L. 580 x .5 x 2.5


= 7250

Impact

= 50000

107250

$$S.M. = \frac{107250 \times 12}{16000} = 80.40 \text{ O.K.}$$



### DESIGN OF TRUNNION

The load on main trunnions equals the resultant of

- (1) The dead load of entire bascule leaf
- (2) The maximum wind load.
- (3) The pinion reaction

Trunnion Girder Reaction

= 108400

Trunnion Wt. 7 x 7854 x 7 x 490

= 2750

111150










SECTION B-B



ELEVATION

Gear train for  
Selsyn Indicator  
pointer


Limit Switch

Indicator for emergency  
operation

SECTION D-D

Generator for Selsyn  
Indicator Pointer







See Sketch on last sheet

$$33645 + 20\% \text{ impact} = 40374$$

$$540000 - 40374 = 499626$$

$$R_1 = \frac{-40374 \cdot 2.75 - 499626 \cdot 2}{6.25} = 178000\#$$

Diaphragm

$$\text{Shear on trunnion girder due to trunnion react.} = 178000 + 2(26779 + 3600) = 239000\#$$

$$\text{Bearing area req'd.} = \frac{239000}{16000} = 15''$$

Shaft 52 (See gearing plans)


$$\text{torque} = 30400 \text{ in}\#$$

$$\text{shearing stress due to torque} = f_s = \frac{M_c}{I_p}$$

$$I_p = \text{polar moment of inertia} = \frac{\pi d^4}{32} = \frac{16 M_t}{\pi d^3}$$

factor of safety

$$d = \sqrt[3]{\frac{16 \cdot 30400 \cdot 10}{3.1416 \times 50000}} = \sqrt[3]{31} = 3.13'' \text{ say } 3\frac{1}{4}'' \text{ dia.}$$

LIVE LOAD GIRDER

$$\text{L.L. Moms. } 20000(86.5) + 10000(76.5) + 15750(63.812) + 15750(48.687) + 15750(33.562) + 21000(26) = 26(R_B)$$

$$R_B = 472000\#$$

$$\text{D.L. Moms. } 11700(87) + 22500(71.875) + 22500(56.75) + 23000(41) + 18000(26) + 280000(3.88) = 26 R_B$$


$$R_B = 247000\#$$

Dead Loads on L.L. Girder

|                |                                  |
|----------------|----------------------------------|
| 1 1/2" Asphalt | $12 \times \frac{85}{12} = 85$   |
| Flooring       | $12 \times 20 = 240$             |
| Stringers      | $12 \times 45 \times 2.42 = 250$ |
| Total          | 799#                             |

Say 800"






Sheet # D-11

LIVE LOAD GIRDER CTD.

$$\begin{aligned} 800(13.16) &= 10550 \\ 800(2.5) &= 2000 \end{aligned}$$

L.L. on L.L. Girder

$$\begin{aligned} 12 \times 80 &= 960 \\ 960(12) &= 11500 \\ 960(2.5) &= 2400 \end{aligned}$$



D.L. Moms. &amp; Shears

$$\text{Mom. at center} = -1000(13) + 10000(10) - 2000(9.7) - 2000(7.3) - 2000(4.8) - 2000(2.4), R = +38600$$

$$\text{Shear (Left of support)} = 10000 - 1000 = 9000$$

$$\text{Shear (Right " " )} = 9000$$

L.L. Moms. &amp; Shears

$$\begin{aligned} \text{Mom. at centre} &= -1200(13) + 12000(10) - 2400(9.7) - 2400(7.3) \\ &\quad - 2400(4.8) - 2400(2.4) \quad R = +46400 \end{aligned}$$

$$\begin{aligned} \text{Shear left of L.L. Bearing} &= 12000 - 1200 = 10800 \\ &\quad 472000 - 12000 = 460000 \end{aligned}$$

$$\text{L.L. shear at left of L.L. supt.} = 460000$$

$$\begin{aligned} \text{L.L. " " Rt. " L.L. " " } &= \\ &\quad 460000 - 472000 + 10800 = 22800 \end{aligned}$$

$$\text{D.L. Mom. left of L.L. Supt.} = -237000(2.7) = -639000$$

$$\begin{aligned} \text{D.L. " at centre of bridge} &= -237000(13.16) + \\ &\quad 247000(10.46) = -540000 \end{aligned}$$

$$\text{L.L. Mom. left of L.L. supt.} = -460000 \times 2.7 = -1,240,000$$

$$\text{L.L. " at centre of bridge} = -460000(13.16) + 472000(10.46) = -1,120,000$$

| LIVE LOAD GIRDER |                     |                     |                    |                      |                     |
|------------------|---------------------|---------------------|--------------------|----------------------|---------------------|
|                  | Moments             |                     |                    | Shears               |                     |
|                  | At L.L. Bearing     | At Bridge           |                    | outside L.L. Bearing | inside L.L. Bearing |
| D. L.            | 638000              | 540000              | D. L.              | 9000                 | 9000                |
| L. L.            | 1240000             | 1120000             | L. L.              | 460000               | 22800               |
| I                | 620000              | 560000              | I                  | 230000               | 11400               |
| Total            | 2498000             | 2220000             | Total              | 699000               | 43200               |
| Eff. Depth       | 5.00'               | 5.00'               | Web Regd. at 10000 | 69.9 <sup>net</sup>  | 43.2 <sup>net</sup> |
| Flg. Stress      | 500000              | 444000              | Use 1 P 66x2       | 33.0 <sup>net</sup>  | 33.0 <sup>net</sup> |
| S.R. @ 16000     | 31.3 <sup>net</sup> | 31.2 <sup>net</sup> | 2 P 58x3           | 43.5                 | 43.5                |
| Sect. Used       | Gr.                 | Net                 | Total              | 76.5 <sup>net</sup>  | 76.5 <sup>net</sup> |
| 1/8 Web          | 5.44                | 5.44                |                    |                      |                     |
| 2 L 8x6x1"       | 26.00               | 25.00               |                    |                      |                     |
| Total            | 31.44               | 30.44               |                    |                      |                     |

### Counterweight Frames

Rear Frame closed & L.L. on  
 $\frac{510000}{26.33} = 19400 \text{ \#/ft.}$

$19400 \div 2 = 9700 \text{ \#/ft. of frame}$

When movable leaf is closed the downward reaction due to anchorage must be added to the above, this equals (of rear frame)

$36000 \div 13.16 = 2730 \text{ \#/ft. of frame}$

At front Ctwt. frame  $16800 \div 13.16 = 1275 \text{ \#/ft. of frame}$

| Rear Ctwt. Frame                 | Front Ctwt. Frame |
|----------------------------------|-------------------|
| Dead Load = 9700                 | 9700              |
| Anchorage React. = 2730          | 1275              |
| I @ 30% of D.L. = 2910           | 2910              |
| Total in \#/ft. of Frame = 15340 | 13885             |

Max. Bend. Mom.  $= \frac{15340 \times 26^2}{8} = 1,300,000 \text{ ft. \#}$  Rear Frame

" " "  $= \frac{13885 \times 26^2}{8} = 1,170,000 \text{ ft. \#}$  Front Frame

Max. Shear  $15340 \times 13.16 = 202000^\#$  @ Rear Frame

Max Shear  $13885 \times 13.16 = 182500^\#$  @ Front Frame

Rear Frame - Span 26 feet

Depth back to back of Ls = 5'-6"

Eff. Depth = 5'-0"

Net web area req'd. =  $\frac{202000}{10000} = 20.20"$

$\frac{20.2}{66} = .306$  use  $\frac{3}{8}"$  Web

Flange stress =  $\frac{1,300,000}{5.0} = 260000^\#$

Req'd. flange area =  $\frac{260000}{16000} = 16.30"$  net

| Flange Used   | Gr.   | Net   |
|---|-------|-------|
| $\frac{1}{8}$ of web = $(\frac{1}{8}) \cdot 375 (64)$ | 3.00  | 3.00  |
| 2 Ls $6 \times 6 \times \frac{1}{2} =$                | 11.50 | 9.50  |
| 1 Cov. Pl $13 \times \frac{1}{2} =$                   | 6.50  | 5.50  |
|   | 21.00 | 18.00 |

Note. Cover plates to be carried full length of girder, both top & bott. flanges

Stiffeners - use 2- $5 \times 3 \times \frac{3}{8}"$  Ls Spaced as shown on sketch.

Front Counterweight Frame

Depth back to back of Ls = 5'-6"

Eff. Depth = 5'-0"

Net web area req'd. =  $\frac{182500}{10000} = 18.250"$

$18.25 \div 66 = .276$  use  $\frac{5}{16}" = .313$

$64 \times \frac{5}{16} = 20.00"$  net

Flange stress =  $\frac{1,170,000}{5.0} = 234000^\#$

Req'd. flange area =  $\frac{234000}{16000} = 14.65"$  net

| Flange Used.  | Gr.   | Net   |
|---|-------|-------|
| $\frac{1}{8}$ web = $(\frac{1}{8}) \cdot 375 \times 64 =$ | 3.00  | 3.00  |
| 2 Ls $6 \times 6 \times \frac{1}{2} =$                    | 11.50 | 9.50  |
| 1 Cov. Pl $13 \times \frac{1}{2} =$                       | 6.50  | 5.50  |
|   | 21.00 | 18.00 |


See sketch

# Lateral System

Sheet # B27

Top lateral

Max. stress comes on lateral system when moving leaf is opened to max opening




Load on concrete = 9700

Encased steel = 300

10000 #/ft. of eq. lateral frame

- = Tension


+ = Comp.



1" = 30000 #

# Lateral System Bottom lateral



Sheet # B28















Scale of stresses 1" = 4000



# Locating Trunnions

It is generally considered customary to so locate the trunnion, that a line passing through the centers of gravity of the moving leaf and the counterweight will pass through the exact center of the trunnion. This condition is difficult to obtain in practice and, too, is not desirable. It is more desirable to so locate the center of gravity of the total load on the trunnion such that the motors are working only half or part of the time of operation.





If the centre of gravity of the total load be eccentric with centre of trunnion, it will fall in one of the four quadrants as shown in sketches A-B-C-D.

In C & D too much power will be consumed. In sketch B the bridge starts open of its own accord, and requires power on closing until the leaf is completely closed. These two conditions are unsatisfactory because in the first case, in the event that the moving leaves become unlocked, the bridge will swing open of its own accord, in the second case, the application of power at the instant that the live load shoes come in contact with their bearings may cause serious over-stress to the machinery or bascule girder.

In case A the bridge will swing closed of its own accord after it is half down, and, therefore, unless it is working against a wind, it will require power only thru the first half of its travel. At the half point the operator will be able to shut off the motors, and devote the rest of the time entirely to the brakes in bringing the leaf to a smooth seating.

The centre of gravity of the total load should be placed at such a distance from the centre of the trunnion, that, it will cause a moment only necessary to rotate the leaf again.

### Locating Trunnions Ctd.

Sheet # B31

the friction of the bearings and machinery. this friction is usually assumed at 15 to 20 percent of the total weight of the moving leaf

This moment =  $Wrk$


$W$  = load on trunnions

$k$  = Coef. of friction of the trunnions on their bearings

$r$  = Radius of trunnions

The dist.  $x$  ahead of the geometric trunnion centre at which centre of gravity of total load is placed is such that  $Wx = Wrk$  i.  $x = rk$  (assuming  $k = 0.20$ ),  $x = .20r$

The distance necessary above the centre of the trunnion is the distance to the intersection of a vertical line <sup>thru C.G.</sup> with a line at an angle of  $\frac{\theta}{2}$  with the vertical axis of the trunnion. With the C.G. in this position the amount of power required to operate will be the same in both directions, and the force holding the bridge open is equal to that required to hold the bridge fully closed.



A slight power is req'd. to operate the leaf through the distance  $h$ . (friction and unbalanced power) This is provided for in the motor design

C.G. of moving leaf.

$$\frac{11700 \times 70 + 22500 \times 54.875 + 22500 \times 39.75 + 23000 \times 29.125 + 18000 \times 9}{97700} = 37.3$$

$$\therefore \begin{aligned} \times \text{ dist. of C.G. of moving leaf} &= 37.3' \text{ from trunnion} \\ \times \text{ dist. of C.G. of counterweight} &= 13.12' \end{aligned}$$

Determining y dist. C.G. of trunnion

$$104.5 \times 4.41 = 461.0$$

$$14.9 \times 2.6 = 38.8$$

$$12.3 \times 9.15 = 112.5$$

$$2.5 \times 8 = 20.0$$

$$2.0 \times 4 = 8.0$$


$$1.0 \times 1.75 = 1.75$$

$$137.2$$

$$642.05$$

$$\frac{642.05}{137.2} = 4.66' \text{ from upper plane of Ct. wt.}$$

$$r = 9'' \quad .20r = 1.80'' = 0.15'$$



$$\theta_2 = 35^\circ$$

$$\tan 35^\circ = \frac{y'}{x'} \quad x = \frac{y'}{.700} = \frac{.15}{.700} = .2142'$$



BASCULE PIER

In finding the maximum footing loads the following items are computed

Dead Loads

- (1) Toe pressure and heel pressure, leaf down
- (2) " " " " " " up


Live Load

- (3) Toe pressure, full live load on approach and fixed portion, no live load on moving leaf.
- (4) Toe pressure and heel pressure, full live load on moving leaf no live load on approach or fixed portion.

- (5) Toe pressure and heel pressure, full live load on approaches, fixed span and moving leaf.

Wind Load (Leaf raised to full open)

- (6) Toe pressure and heel pressure with wind from river side
- (7) Toe pressure and heel pressure with wind from approach side

Legend

- (a) = Dead load of superstructure
- (b) = Dead load of pier
- (c) = Live load reaction from approach
- (d) = Live load reaction from fixed portion
- (e) = Live load on moving leaf
- (f) = Wind load from approach
- (g) = Wind load from river

Dead Loads of pier

$$\text{Base } 38 \times 10 \times 50 \times 150 =$$

$$34 \times 22 \times 50 \times 150 =$$

$$\text{Deduct } 34 \times \frac{1}{4} (46^2 \times .7854) 150 =$$

$$2,850,000$$

$$5,610,000$$

$$8,460,000$$

$$2,122,875$$

$$6,337,125$$

# Fixed Deck

$$\begin{array}{rcl} \text{D.L.} & = & 10000 \# \\ \text{L.L. } 13 \times 27 \times 80 & = & 28080 \# \\ \text{I} & = & 8424 \# \end{array} \left. \vphantom{\begin{array}{rcl} \text{D.L.} \\ \text{L.L.} \\ \text{I} \end{array}} \right\} 36.504 \#$$

## Approach Span Reactions

$$\begin{array}{rcl} \text{D.L.} & = & 120000 \# \\ \text{L.L.} & = & 30100 \# \\ \text{I} & = & 9030 \# \\ \hline & = & 159130 \# \end{array}$$

### Item (1)

Taking moments about "a"

$$\frac{-120000(2.5) - 6,337,125(20) - 247000(35)}{6,704,125} = X$$

$$\frac{-300000 - 126,742,500 - 8,645,000}{6,704,125} = X$$

$$X = \frac{135,687,500}{6,704,125} = 20.5'$$

$$K_1 = \frac{2P(2l - 3l_2)}{l^2} = \frac{2(6,704,125)[2(39) - 3(18.5)]}{(39)^2}$$

$$= \frac{13,408,250[78 - 55.5]}{1520} = 198000 \#$$

$$K_2 = \frac{2P(2l - 3l_2)}{l^2}$$

$$= \frac{13,408,250(78 - 61.5)}{1520} = 145500$$

### Item (2)

Taking moments about "a"


$$\frac{-120000(2.5) - 6,337,125(20) - 247000(27)}{6,704,125} = X$$

$$X = 19.9'$$

$$K_1 = \frac{13,408,250[78] - 3(19.9)]}{1520} = 183000 \#$$

$$K_2 = \frac{13,408,250[78 - 3(19.9)]}{1520} = 162000 \#$$

Note - that values for  $K_1$  &  $K_2$  cover half width of bascule pier



Item (3)


Taking moments about 'a'

$$x = \frac{-39100(2.5) - 36500(20)}{75600} = 10.94'$$

$$K_1 = \frac{6(75600)9}{(39)^2} + \frac{75600}{39} = 4628$$

$$= 4628$$


$$K_2 = -\frac{6(75600)9}{(39)^2} + \frac{75600}{39} = -752$$



Item (4)

$$K_1 = \frac{944000(78 - 12)}{1520} = 41000\#$$

$$K_2 = \frac{944000(78 - 105)}{1520} = -4347\#$$




Item (5)

Taking moments about 'a'

$$x = \frac{-39100(2.5) - 36500(20) - 472000(35)}{547600} = 31.6'$$

$$K_1 = \frac{1095200(78 - 22.2)}{1520} = 40300\#$$

$$K_2 = \frac{1095200(78 - 94.8)}{1520} = -12100\#$$



Item (6)

$$\text{Wind } 30 \times 60 \times 26 = \frac{46800}{2}$$


$$= 23400$$

Taking Moments about a.

$$P = \frac{23400(55)}{29} = 46000\#$$

$$K_1 = \frac{92000(78 - 33)}{1520} = 2730\#$$

$$K_2 = \frac{92000(78 - 84)}{1520} = -363\#$$



Item (7) Wind from approach


Taking Moments about b

$$P = \frac{23400(55)}{11} = 117000\#$$

$$K_1 = \frac{234000(78 - 33)}{1520} = 6930\#$$

$$K_2 = \frac{234000(78 - 84)}{1520} = -925\#$$


In order to obtain the max. stresses the various items will be combined.  
[Combination of 2-3 & 6]



By observation, it can be seen, that by combining either item (1) or item (2) with any of the other items either individually or in groups the pier will be stable.

Note: Stresses are for half width of pier for all diagrams.







# — DESIGN OF OPERATING MACHINERY —

Sheet #M-1

## General Data

|  |         |
|--|---------|
| Distance center to center of trunnions | 140'-0" |
| " " " " " main girders                 | 26'-4"  |
| Rack Radius                            | 20'-0"  |
| Angle of opening                       | 70°-0'  |
| Dead load (moving) one girder only     |         |
| River arm                              | 98500#  |
| Rear arm                               | 280000# |
| Total weight                           | 378500# |

Distance center of gravity river arm to trunnion

$$367200 \div 98500 = 37.3'$$

Distance center of gravity rear arm to trunnion = 13.0'

Area of floor (one girder)  $26.5 \times 70 = 1855 \text{ sq. ft.}$

Distance center of gravity of floor area from trunnion = 35.0'

Coef. of friction (Forged steel trunnions in phosphor bronze bushings) = 15%

Max. starting force at the rack circle - The tangential force at the rack circle applied through the operating pinion must be sufficient to overcome the following resistances.

- (1) Inertia of the moving mass
- (2) Wind resistance
- (3) Frictional resistance

Inertia of the moving mass

$m$  = Equivalent mass at the rack circle

$a$  = Acceleration in feet per second

$$F = ma.$$

If a weight "W" has its center of gravity c distance from the center of rotation, the equivalent mass reduced to a rack radius "r" =  $M = \frac{Wc^2}{32.2 r^2}$ ;  $Mr^2 = \frac{Wc^2}{32.2}$

For River Arm.

$$Mr^2 = (98500 \times 37.3^2) \div 32.2 = 4,260,000$$

For Rear Arm

$$Mr^2 = (280000 \times 13^2) \div 32.2 = 1,470,000$$

$$5,730,000$$

$$M = 5,730,000 \div 400 = 14,300 \text{ ft. \#}$$

For 70° angular rotation the length of travel on the rack =  $[(2\pi) 20(70^\circ)] \div 360^\circ = 24.5 \text{ ft. approx.}$   
 Assuming total time of opening at 2 min, the first 30 sec. as the period of acceleration; the last 30 sec. as the time of retardation; & the intermediate 60 sec. as the period of uniform motion.

$$\text{Uniform velocity} = \frac{24.5}{\frac{30}{2} + 60 + \frac{30}{2}} = .272 \text{ ft. per sec.}$$

$$\text{Acceleration} = \frac{0.272}{15} = .0181 \text{ ft. per sec.}^2$$

$$F = ma = 2 \times 14300 \times 0.0181 = 518 \#$$

$$\text{Wind resistance } 15^\# \text{ wind } \frac{1855 \times 15 \times 35}{20} = 48800$$

Frictional resistance

|                            |          |
|----------------------------|----------|
| Load on trunnion Dead load | { 378500 |
| Wind load on pinion        | { 378500 |
| Total                      | 48800    |
|                            | 805800   |

Frictional force reduced to the periphery of the rack circle. =

$$\frac{(805800)(9)(0.15)}{240} = 4540 \#$$

Total Tangential Force at Rack Circle

|            |        |
|------------|--------|
| Inertial   | = 1036 |
| Wind       | 48800  |
| Frictional | 4540   |
| Total      | 54376  |

Say 54000 #

$$\text{Frict. \& Inertional Resist. alone} = 3436$$

$$5^\# \text{ wind resistance} = 16260$$

$$\text{Total (say 19700)} = 19696$$

$$\text{Frict. \& Inertional Resist.} = 3436$$

$$10^\# \text{ Wind resistance} = 32520$$

$$\text{Total (say 36000)} = 35956$$

Sheet no. \_\_\_\_\_

## Design of Rack & Main Drive Pinion (Involute)

Assume cir. pitch, for rack, of 3", a tooth face of 8" & a pinion of 17 teeth

$$S = \frac{54000}{3 \times 8 \times .096} = 23400 \text{ #/in}^2$$

For holding (not operating) against a 15<sup>#</sup> wind the inertial resistance would be zero. frictional resistance would be

$$S = \frac{(48800 - 4500)}{3(8)(.096)} = 20100 \text{ #/in}^2$$

For operating against a 10<sup>#</sup> wind

$$S = \frac{36000}{3(8)(.096)} = 15600 \text{ #/in}^2$$

Assuming a 20000 #/in<sup>2</sup> working stress for forged steel. Stress due to max. wind =  $\frac{2600}{20000} = 13\%$  over stress (which is not excessive)

Number of teeth in a full rack circle of 20 ft. radius =  $[20 \times 3.14 \times 12] \div 3 = 252$

∴ Tooth stress in rack =

$$S = \frac{54000}{3 \times 8 \times .15} = 15,000 \text{ #/in}^2 \text{ which is safe}$$

### GEARING DESIGN

Max. tangential force applied at the rack circle by the main drive pinion = 52000 # due to wind load

Pitch radius of main drive pinion =  $\frac{3 \times 17}{2(3.14)} = 8.1$  inches

Max. torque on the " " " =  $54000 \times 8.1 = 448000 \text{ #/in}$

Due to 10<sup>#</sup> wind " " " =  $36000 \times 8.1 = 292000 \text{ #/in}$

" " 5<sup>#</sup> " " " =  $20000 \times 8.1 = 162000 \text{ #/in}$

" " 0<sup>#</sup> " " " =  $3436 \times 8.1 = 28000 \text{ #/in}$

or 36500 ft. #; 24300 ft. #, 13500 ft. #, 2330 ft. # respectively

Max. lineal velocity of the pinion = .272 ft. per sec  
= 16.32 ft. per min

Circumference of main drive pinion  
 $= \frac{2 \times 3.14(8.1)}{2} = 4.23 \text{ ft. at the pitch circle}$

Operating Power =  $\frac{2\pi(\text{torque})(\text{R.P.M.})}{33000} = 26.75$

There are four sets of pinions & gearing between main drive pinion, and the motor shaft. Since there are two sets of mitre gears, an average efficiency of 90% was assumed.  
 $(.90)^2 = .81$        $100 \div .81 = 123\%$  or 23% extra power to overcome friction loss.

| Wind Load (lb)   | H. P. Req'd. | Torque + 50%<br>ft. # Reduced to<br>Pinion Speed |
|--|--------------|--|
|  | One Leaf     | One Leaf   |
| 0  | 1.72         | 3500   |
| 5  | 9.95         | 20300  |
| 10   | 17.90        | 36400  |
| 15   | 40.00        | 52800  |
| For holding not operating<br>against a 15# wind<br>the values become $\frac{46400}{52000}$<br>of the last values above | 35.80        | 47000  |

The motor selected must fulfill the following requirements

- (1) It must open the leaf full in the reg'd. opening time against a 10# wind.
- (2) The max. torque developed should be at least 50% greater than reg'd. to hold the leaf against a 15# wind.
- (3) The motor should develop a max. torque 10% greater than is reg'd. to operate the leaf against a 10# wind.

A 30 H. P motor @ 580 R. P. M. full load. 440 volt  
 A. C. Induction motor. Full load torque = 188 ft. #  
 Max. torque = 525 ft. #



$580 \div 3.86 = 150 =$  Gear reduction between main pinion and motor shaft.

Motor torques developed

Operating against 10# wind =  $\frac{36400}{150} = 343 \text{ ft. \#}$

Holding against 15# wind =  $\frac{47000}{150} = 313 \text{ ft. \#}$

TABLE I

| TABULATED REQUIREMENTS OF MOTOR (To satisfy the above) |                  |                    |       |
|--|------------------|--------------------|-------|
| Conditions as listed above                             | Full Load Torque | Max Torque         | Power |
| 1  | 343 ft. \#       |                    | 17.90 |
| 2  |                  | $313 + 50\% = 480$ |       |
| 3  |                  | $343 + 10\% = 377$ |       |

### DESIGN OF GEAR TRAIN

(See drawings)

Speed of Pinion P1 & Gear G2 = 3.86 R.P.M

" " " P2 " MG3 =  $3.86 \left( \frac{61}{17} \right) = 13.80$  " " "

" " " MP3 " MG4 =  $13.80 \left( \frac{53}{17} \right) = 43.20$  " " "

" " " MP4 " G5 =  $43.20 \left( \frac{45}{23} \right) = 84.20$  " " "

" " " P5 " G6 =  $84.2 \left( \frac{128}{19} \right) = 566.0$  " " "

Motor was selected at 580 R.P.M which is as close as can be worked out practically

Exact gear reduction between main pinion and the motor shaft =  $\left( \frac{61}{17} \right) \left( \frac{53}{17} \right) \left( \frac{45}{23} \right) \left( \frac{128}{19} \right) = 158$

Exact torques required at the motor shaft.  
10# wind one leaf =  $\frac{36400}{158} = 231 \text{ ft. \#}$

Holding against 15# wind =  $\frac{47000}{158} = 298 \text{ ft. \#}$

These required torques are less than the computed torques and also less than the tabulated requirements as scheduled in Table I

Sheet M6

Gears to be of cast steel, pinions of forged steel  
Gear Design (using 20° Involute teeth)

(G2)  $p = 2''$ ;  $f = 5\frac{1}{2}''$ ;  $y = .134$

Pitch Dia. (for 61 tooth gear)

$= \frac{61 \times 2}{3.14} = 38.8 \text{ inches}$

$p$  = circular pitch

$f$  = face width

$y$  = From Lewis Table

$F$  = Tangential pres.

$F = 54000 \frac{16.2}{38.8} = 22600 \#$

Tooth speed at pitch circle  $= 3.86 \pi \left( \frac{28.8}{12} \right) = 29.1 \text{ ft. per min.}$

Efficiency of gears (incl. journal friction) at 93%

$F = \frac{22600}{0.93} = 24300 \text{ incl. friction loss}$

$s = \frac{24300}{5.5 \times 2 \times .134} = 16500 \#/\text{in}^2$  which is satisfactory

Tooth stress for 10# wind  $= \frac{36000}{52000} \times 16500 = 11400 \#/\text{in}^2$

(P2)  $p = 2''$ ;  $f = 7''$ ;  $y = .096$ ; No. of teeth = 17

pitch dia.  $= 17 \times 2 \div 3.14 = 10.8''$

$F = 24300$

$s = \frac{24300}{7 \times 2 \times .096} = 18000 \#/\text{in}^2$  O.K

(MG3) No. of teeth = 53;  $p = 1\frac{3}{4}''$ ;  $f = 3\frac{1}{2}''$ ; R.P.M. = 13.80;

$y = .131$

pitch dia.  $= \frac{53 \times 1.75}{3.14} = 29.6''$

$F = 24300 \left( \frac{10.8}{29.6} \right) = 8850 \#$

Tooth speed  $= 13.80 \pi \left( \frac{33.8}{12} \right) = 12.2 \text{ ft. per sec.}$

Efficiency of gears (incl. journal friction) at 90%

$F = \frac{8850}{.90} = 9800 \text{ incl. friction loss}$

$s = \frac{9800}{3.5 \times 1.75 \times .13} = 12300 \#/\text{in}^2$

(MP3) 17 teeth;  $p = 1\frac{3}{4}''$ ;  $f = 3\frac{1}{2}''$ ; R.P.M. = 43.2;  $y = .096$

$s = \frac{12300}{1.75 \times 3.5 \times .096} = 21400 \#/\text{in}^2$

pitch dia.  $= \frac{17 \times 1.75}{3.14} = 9.45$

(M54) No of teeth 45,  $p = 1\frac{1}{2}$ ",  $f = 3$ ", R.P.M. = 43.2,

$$y = .127$$

$$\text{pitch dia.} = \frac{45 \times 1.5}{3.14} = 21.5"$$

$$F = 9800 \left( \frac{9.45}{21.5} \right) = 4300$$

$$\text{Tooth speed} = (43.20) \pi \left( \frac{21.5}{12} \right) = 242.0 \text{ ft. per min.}$$

$$\text{Eff. of gears} = 82\%$$

$$F = \frac{4300}{.88} = 4880 \text{ incl. friction loss}$$

$$S = \frac{4880}{3 \times 1.5 \times .127} = 8500 \text{ #/D.}$$

(M P4) 23 teeth;  $p = 1\frac{1}{2}$ ",  $f = 3$ ", R.P.M. = 84.2,  $y = .106$   
pitch dia =  $(23 \times 1.5) \div 3.14 = 11"$

$$S = \frac{4880}{1.5 \times 3 \times .106} = 10450 \text{ #/D.}$$

(G5) 128 teeth,  $p = 1$ ",  $f = 4$ ", R.P.M. = 84.2;  $y = .142$   
pitch dia =  $(123 \times 1) \div 3.14 = 39.2"$

$$F = 4880 \left( \frac{11}{39.2} \right) = 1365 \text{ #}$$

$$\text{Tooth speed} = (84.2) \pi \left( \frac{39.2}{12} \right) = 8610$$

$$\text{Eff.} = 86\%$$

$$F = 1365 \div 0.88 = 1550 \text{ incl. friction loss}$$

$$S = 1550 \div 4 \times 1 \times .142 = 2730 \text{ #/D.}$$

(P5) 19 teeth;  $p = 1$ ";  $f = 4\frac{1}{2}$ ";  $y = .100$   
pitch dia. =  $19 \times 1 \div 3.14 = 6.05"$

$$S = \frac{2730}{4.5 \times 1 \times 1} = 6050 \text{ #/D.}$$

(G6) 123 teeth;  $p = 1$ ";  $f = 4$ ";  $y = .143$   
 $F = 24300 \left( \frac{10.8}{39.2} \right) = 6700 \text{ #}$

$$\text{pitch dia.} = 123 \times 1 \div 3.14 = 39.2$$

$$F = 6700 \div .90 = 7440 \text{ #}$$

$$S = \frac{7440}{4 \times 1 \times .143} = 13000 \text{ #/D.}$$

(G7) 73 teeth;  $p = 1$ ";  $f = 4$ ";  $y = .138$

$$F = 7440 \text{ pitch dia.} = 73 \times 1 \div 3.14 = 23.2"$$

$$S = 7440 \div 4 \times 1 \times .138 = 13450$$



#  
Sheet M8

(P7) 21 Teeth;  $p=1$ ;  $f=4\frac{1}{2}$ ;  $y=.104$

$$\text{pitch dia.} = 21.1 \div 3.14 = 6.68"; F=7440 \#$$
$$S = 7440 \div 4.5 \times 1 \times .104 = 16500 \#/\text{in}$$

(P8) 19 Teeth;  $p=1$ ;  $f=5\frac{1}{2}$ ;  $y=.100$

$$\text{pitch dia.} = 19.1 \div 3.14 = 6.08"$$

$$F = (7440 \times 21) \div 19 = 8210 \#$$

$$S = 9120 \div 5.5 \times 1 \times .1 = 16600 \#/\text{in}$$

$$F = 8210 \div .90 = 9120 \#$$

(I8) 51 Teeth;  $p=1$ ;  $f=5.5$ ; pitch dia. = 16.234";  $F=9120$

(G8) 66 Teeth;  $p=1$ ;  $f=5.5$

$$\text{pitch dia.} = 21"$$

$$F = (9120 \times 16.234) \div 21 = 7040 \#$$

$$F = 7040 \div .95 = 7450 \#$$


TABLE OF GEAR CALCULATIONS

(Type of tooth 20° Involute)

| Gear No | (P) Circular Pitch Inches | Number of Teeth | Pitch Dia. in Inches | R.P.M | Tooth Speed in Ft. per Min. | Est. Eff. Gear & Journal (Per Cent) | Total Pressure        |                         | Torque on Shafting in # | Y, Lewis Formula Factor | Material     | Face Width | Unit Stress (lbs.) |
|---------|---------------------------|-----------------|----------------------|-------|-----------------------------|-------------------------------------|-----------------------|-------------------------|-------------------------|-------------------------|--------------|------------|--------------------|
|         |                           |                 |                      |       |                             |                                     | Without Gear Friction | Including Gear Friction |                         |                         |              |            |                    |
| R-1     | 3"                        | 252             |                      |       |                             |                                     |                       |                         |                         |                         |              | 8"         |                    |
| P-1     | 3"                        | 17              | 16.2                 | 3.86  |                             | .93                                 |                       |                         |                         |                         | Forged Steel | 8"         | 15600              |
| G-2     | 2"                        | 61              | 38.8                 | 3.86  | 29.1                        | .93                                 | 22600                 | 24300                   | 472000                  | .134                    | Cast "       | 5½"        | 16500              |
| P-2     | 2"                        | 17              | 10.8                 | 13.80 | 39.0                        |                                     | 22600                 | 24300                   | 131500                  | .1096                   | Forged "     | 7"         | 18000              |
| MG-3    | 1¾"                       | 53              | 29.6                 | 13.80 | 12.2                        | .90                                 | 8850                  | 9800                    | 195000                  | .131                    | Cast "       | 3½"        | 12300              |
| MP-3    | 1¾"                       | 17              | 9.45                 | 43.20 | 12.2                        |                                     | 8850                  | 9800                    | 46300                   |                         | Forged "     | 3½"        | 21400              |
| MG-4    | 1½"                       | 45              | 21.5                 | 43.20 | 2420                        | .85                                 | 4300                  | 4880                    | 52400                   | .127                    | Cast "       | 3"         | 8500               |
| MP-4    | 1½"                       | 23              | 11.0                 | 84.20 | 2420                        |                                     | 4300                  | 4880                    | 26900                   | .106                    | Forged "     | 3"         | 10450              |
| G-5     | 1"                        | 128             | 39.2                 | 84.20 | 8610                        | .90                                 | 1365                  | 1550                    | 30400                   | .142                    | Cast "       | 4"         | 2730               |
| P-5     | 1"                        | 19              | 6.05                 | 566.0 | 8610                        | .90                                 | 1365                  | 1550                    | 4690                    | .100                    | Forged "     | 4½"        | 6050               |
| G-6     | 1"                        | 123             | 39.2                 | 566.0 | -                           | .90                                 | 6700                  | 7440                    | 14500                   | .143                    | Cast "       | 4"         | 13000              |
| G-7     | 1"                        | 73              | 23.2                 |       | -                           | .90                                 | 6700                  | 7440                    | 86200                   | .138                    | Forged "     | 4"         | 13450              |
| P-7     | 1"                        | 21              | 6.68                 | 1400  | -                           | .90                                 | 6700                  | 7440                    | 24900                   | .104                    | Cast "       | 4½"        | 16500              |
| P-8     | 1"                        | 19              | 6.08                 | 1400  | -                           | .90                                 | 8210                  | 9120                    | 27400                   | .100                    | Forged "     | 5½"        | 16500              |
| G-8     | 1"                        | 66              | 21.00                | -     | -                           | .95                                 | 7040                  | 7450                    |                         |                         |              |            |                    |
| I-8     | 1"                        | 51              | 16.23                | -     | -                           |                                     | 8210                  | 9120                    |                         |                         |              |            |                    |

Check on motor shaft P5,  $\frac{4690}{12} = 390$  ft. #  
 $390 \times \text{gear ratio} = 390 \times 158 = 61600$  ft. # approx.








# Design of Handbrakes

Sheet No 10



Applying Force "F" to the lever as shown above  
 $(T_0 + T_1)r_1 = \frac{F_4 r_2}{r_3}$ ,  $T_0 + T_1 = \frac{F_4 r_2}{r_3 r_1}$

Assuming belt is about to slip,  
 Diagram B is a free body diagram, taken from diagram A, of an element of brake belt of length  $ds$ . The forces acting on this element are  $T$  &  $T + dT$  at the ends & reaction of the brake cylinder.


$$p = \frac{T}{r}$$

Refer to diagram B

$$dN = \mu p ds = dT$$

$$ds = r d\theta$$

$$\frac{dT}{T} = \frac{\mu p ds}{T} = \frac{\mu p r d\theta}{T} = \frac{\mu d\theta (pr)}{T} = \mu d\theta$$



Design of Hand brake C-1

$\frac{dT}{T} = u d\theta$  Integrating this equation the relation between  $T_1$  &  $T_0$  may be found

$$\int_{T_1}^{T_0} \frac{dT}{T} = \int_0^\theta u d\theta$$

$$\log_e \frac{T_0}{T_1} = u\theta \quad \text{or} \quad \frac{T_0}{T_1} = e^{u\theta}$$

$$T_0 = T_1 e^{u\theta}$$

where  $e$  is the base of Napierian logarithms 2.71828

$u$  = Coefficient of friction

$\theta$  = The angle of contact in radians

Substituting in our original equation

$$T_0 + T_1 = \frac{F_1 r_1 r_2}{r_3 r_1} = T_0 (1 + e^{u\theta}) = \frac{F_1 r_1 r_2}{r_3 r_1}$$

$$\text{Torque on brake band} = (T_1 - T_0) r_0 = T_0 (e^{u\theta} - 1) r_0$$

by subst.

$$\text{Braking Torque} = \left( \frac{F_1 r_1 r_2}{r_1 r_3} \right) \left( \frac{e^{u\theta} - 1}{e^{u\theta} + 1} \right) r_0$$

Values of  $e^{u\theta}$  for various angles of contact are given below (based on assumed coef. of friction of 20 percent)

Values of  $\theta$  in degrees

Value of  $e^{u\theta} = e^{0.20\theta}$

|     |      |
|-----|------|
| 140 | 1.63 |
| 160 | 1.74 |
| 180 | 1.87 |
| 200 | 2.01 |
| 220 | 2.16 |
| 240 | 2.31 |
| 270 | 2.57 |
| 300 | 2.85 |

Braking torque necessary to hold the moving leaf against a 15# wind =

$(48800 - 4500) 19.57 = 876,951 \text{ in}\#$  (approx) on the main pinion shaft.

Reduced to the speed of shaft 36

$$876,951 \times \frac{73}{123} = 520,000 \text{ in}\#$$

Design of Hand Brakes Ctd.

Assuming a maximum pull at the end of the brake lever equal to 100#

Taking

$$r_1 = 3''$$

$$r_2 = 24''$$

$$r_3 = 3''$$

$$r_4 = 60''$$

$$r_5 = 9''$$

$$Q^{40} = 2.57$$

$$F = 100\#$$

$$\text{Braking Torque} = \left[ \frac{(100)(60)(24)}{3(3)} \right] \left[ \frac{2.57-1}{2.57+1} \right] 9 = 63,400 \text{ in}\#$$

which is satisfactory.

Centre Lock Mechanism

Total shearing stress (2 Girders) transmitted by the centre lock = 20000#

Assuming coef. of friction of 30%

pull on centre lock = .30(20000) = 6000#

Assuming length of time req'd. in locking or unlocking the bridge as 10 seconds

Power developed = (Travel of locking pins = 62")

$$\frac{6000 \times 62}{10} = 3900 \text{ in}\# \text{ per sec.}$$

$$\text{or } \frac{(3900)(60)}{12} = 19500 \text{ ft}\# \text{ per min.}$$

$$\frac{19500}{33000} = 0.59 \text{ H.P.}$$

Assuming overall eff. of 60%

$$\frac{.59}{.60} = .985 \text{ H.P. or approx. 1.0 H.P.}$$

An electric motor will be used placed at the end of the moving leaf.

Inasmuch as there is very little difference in the cost between a 1 H.P & a 3 H.P electric motor




and, too, since an excess of power is desirable in this particular case, an electric motor of 3 H.P. will be selected. A.C. running at a full load speed of 1,125 R.P.M.


The complete operation of locking or unlocking the bridge requires a one-half revolution of the crank shaft and requires a time interval of 10 sec.. During this time the motor makes approx.  $1125 \times \frac{10}{60} = 188$  rev.


Gear reduction,  $\therefore = 188 \div \frac{1}{2} = 376$

A spur gear of a reduction of 3 to 1 together with a speed transformer of a ratio of 65:1 will be adopted.



Sheet D-12





Scale of 100 ft.  
 Scale of 1000 ft.  
 1:100,000 ft.  
 1:100,000 ft.

Scale of 100 ft.  
 Scale of 1000 ft.  
 1:100,000 ft.  
 1:100,000 ft.

Sheet D-17



# Design Of Approach Spans

Live Load.

End Span - Large Wheel at Center  
(Suspended Girder)

R1

$$6900(60) + 13800(46.67) + 21000(33.33) + 17300(20) + 13800(6.68)$$

$$= \frac{414000 + 644000 + 700000 + 346000 + 92300}{72800}$$

$$R1 = \frac{2,196,300}{72800} = 30100 \#$$

$$\text{Hinge} = 72800 - 30100 = 42700 \#$$

$$R3 = 42700 + 13800 = 56500 \#$$

Cont. Mom. L.L

$$42700(20) + 13800(6.68)$$

$$= 854000 + 92100 = 946100 \text{ ft. \#}$$

$$M_a = 30100(13.33) - (6900)(13.33)$$

$$= 401000 - 92000 = 309000 \text{ ft. \#}$$

$$M_b = 30100(26.66) - 6900(26.66) - 13800(13.33)$$

$$= 802000 - 184000 - 184000$$

$$= 434000 \text{ ft. \#}$$

$$M_d = -42700(6.68) = -285000 \text{ ft. \#}$$

$$M_c = -42700(20) - 13800(13.33) = 854000 - 184000 = 670000 \text{ ft. \#}$$

L.L. Shears


$$\text{Between } R_1 \text{ \& } a \quad 30100 - 6900 = 23200$$

$$a \text{ " } b \quad 23200 - 13800 = 9400$$

$$\text{Hinge to } d \quad = 42700$$

$$d \text{ to } c \quad 42700 - 13800 = 28900$$

$$c \text{ " } b \quad 28900 - 17300 = 11600$$



End Span, D.L.  
(Suspended Girder)

Sheet A-2

H.R. & Girder

$$= 1400 \times 13.33 = 18700$$

$$170 \times 13 \times 13.33 = 29500$$

$$48200 \#$$

$$\frac{24000(60) + 48000(46.67) + 48000(33.33) + 48000(20.01) + 48000(6.68)}{60}$$

$$= \frac{1440000 + 2,240,000 + 1,600,000}{60} +$$

$$\frac{960000 + 320000}{60}$$

$$R1 = \frac{6,560,000}{60} = 109400 \#$$

$$R2 = 216000 - 109400 = 106,600 \#$$

$$M_a = 109400(13.33) = 1,460,000 \text{ ft.}\#$$

$$M_b = 109,400(26.66) - 48000(13.33) = 2,280,000 \#$$

$$M_c = 109,400(39.99) - 48000(26.66) - 48000(13.33) = 2,448,000 \#$$


$$M_d = 106,600(6.68) = 713,000 \#$$

Cantilever Moments





$$M_{R3} = 106,600(20) + 48000(13.33) = 2,772,000 \text{ ft.}\#$$

D.L. Shears

|         |        |
|---------|--------|
| R1 to a | 109400 |
| a " b   | 61400  |
| b " c   | 13400  |
| R2 " d  | 106600 |



# Summary of Stresses Suspended Girder


| R-1   | a   | b   | c   | d   |
|---|---|---|---|---|
| Shears D.L.                                     | 109400  | 61400   | 13400   | 106600  |
| " L.L.  | 23300   | 9400  | 28900   | 42700   |
| I   | 6990  | 2820  | 8670  | 12810   |
| Total   | 139690  | 73620   | 50970   | 162110  |
| Sect. Req'd. 10000# Gr.                         | 13.96"  | 7.36"   | 5.09"   | 16.21"  |
| Web Used  | 69x <sup>3</sup> / <sub>8</sub> =25.9   | 52x <sup>3</sup> / <sub>8</sub> =19.5   | 46x <sup>3</sup> / <sub>8</sub> =17.2   | 53x <sup>3</sup> / <sub>8</sub> =19.8   |
| Moments ft. #                                   |   |   |   |   |
| " D.L.  | 1251000   | 1786000   | 1617000   | 788000  |
| " L.L.  | 309000  | 434000  | 670000  | 285000  |
| " I   | 92700   | 130200  | 201000  | 85500   |
| " Total   | 1652700   | 2350000   | 2488000   | 1158000   |
| Eff. Depth                                      | 5.46'   | 4.03'   | 3.53'   | 4.12'   |
| Top Flange Stress                               | 302700  | 583000  | 705000  | 281000  |
| Bott " "  | 305000  | 583000  | 705000  | 281000  |
| Flange Req'd.                                   | net. 19.06  | 36.4" net   | 44.1" net   | 17.56" net  |
| Sect. Used                                      | Gr. Net   | Gr. Net   | Gr. Net   | Gr. Net   |
| '8 Web  | 3.23 3.23   | 2.43 2.43   | 2.15 2.15   | 2.48 2.48   |
| 2 Ls 6x6x <sup>3</sup> / <sub>4</sub> "         | 16.88 13.88   | 16.88 13.88   | 16.88 13.88   | 16.88 13.88   |
| 1 P 13x1"                                       | 13.00 11.00   | 13.00 11.00   | 13.00 11.00   | 13.00 11.00   |
| 1 P 13x1"                                       |   | 13.00 11.00   | 13.00 11.00   |   |
| 2 Ps 8x <sup>5</sup> / <sub>8</sub> " (Side Ps) |   |   | 10.00 7.00  |   |
|   | 33.11 28.11   | 45.31 38.31   | 55.03 45.03   | 32.36 27.36   |
| Flange Sections                                 |  |  |  |  |



# Center Span

L.L.

$$R3 = 13800(80) + 13800(66.67) + 13800(53.33) + 20000(40) + 13800(26.68) + 13800(13.33) \div 80$$



$$\frac{1,104,000 + 920,000 + 735,000 + 800,000 + 369,000 + 184,000}{80} = R3$$

$$R3 = \frac{4,112,000}{80} = 51,400 \#$$

$$R4 = 51,400$$

$$M_f = 51,400(13.33) = 685,000 \#$$

$$M_g = 51,400(26.66) - 13,800(13.33) = 1,189,800 \#$$

$$M_h = 51,400(40) - 13,800(26.66) - 13,800(13.33) = 1,502,500 \#$$

## L.L. Shears

$$R3 \text{ to } f = 51,400$$

$$f \text{ to } g = 51,400 - 13,800 = 37,600$$

$$g \text{ " } h = 37,600 - 13,800 = 23,800$$


## D.L. Shears (See Diagram Sheet A-5)

$$e \text{ to } R3 = 171,000$$

$$R3 \text{ " } f = 159,000$$

$$f \text{ " } g = 106,000$$

$$g \text{ " } h = 53,000$$








Center Span D.L.

$$\begin{aligned}
 R_3 &= R_4 \\
 &= 118000 + 4.5(53000) = 356000 \# \\
 MR_3 &= 118000(20) - 53000(13.33) = 3026500 \text{ ft}\# \\
 M_f &= 118000(33.33) - 53000(26.66) - 53000(13.33) + 356500(13.33) = -1291000 \text{ ft}\# \\
 M_g &= -118000(46.66) - 53000(40) - 53000(26.66) - 53000(13.33) + 356000(26.66) = -231000 \text{ ft}\# \\
 M_h &= -118000(60) - 53000(53.32) - 53000(40) - 53000(26.66) - 53000(13.33) + 356000(40) = 109000 \text{ ft}\#
 \end{aligned}$$

See Sheet A6 for Tabulation of Stresses



See Sheets A1 & A2 for cantilever Stresses

Summary of Stresses  
Intermediate Girder


|  | e   | R3  | f  | g   | h   |
|--|---|---|--|---|---|
| Shear D.L.   | 118000  | 171000  | 159000   | 106000  | 53000   |
| " L.L.   |   | 56500   | 51400  | 37600   | 23800   |
| " I  | 35400   | 16950   | 15420  | 31800   | 15900   |
| " Total  | 153400  | 244450  | 225820   | 175400  | 92700   |
| Sect. Req'd.   | 15.34 <sup>Gr.</sup>  | 24.44 <sup>Gr.</sup>  | 22.58 <sup>Gr.</sup>   | 17.54 <sup>Gr.</sup>  | 9.27 <sup>Gr.</sup>   |
| Web Used   | 66x <sup>3</sup> / <sub>8</sub> "=24.75   | 114x <sup>3</sup> / <sub>8</sub> "=42.75  | 66x <sup>3</sup> / <sub>8</sub> "=24.75  | 48x <sup>3</sup> / <sub>8</sub> "=18"   | 46x <sup>3</sup> / <sub>8</sub> "=17.25   |
| Moms. Ft.#   |   |   |  |   |   |
| " D.L.   |   | 3026500   | 7291000  | -231000   | +109000   |
| " L.L.   |   | -946000   | +685000  | +189800   | +502500   |
| " I  |   | -283800   | +205500  | +356940   | +450750   |
| " Total  |   | 4256300   | -400500  | +1015740  | +2062250  |
| Eff. Depth   | 5.21  | 9.21  | 5.21   | 7.08  | 3.54  |
| Top Flg. Stress  |   | 462000  | 76800  | 143500  | 583000  |
| Bot " "  |   | 464000  | 77000  | 143000  | 583000  |
| Flange Req'd.  |   | 29 <sup>net</sup>   | 4.81 <sup>net</sup>  | 8.94 <sup>net</sup>   | 36.43 <sup>net</sup>  |
| Sect Used  | Gr. Net   | Gr. Net   | Gr. Net  | Gr. Net   | Gr. Net   |
| <sup>3</sup> / <sub>8</sub> Web                                  | 3.09 3.09   | 5.35 5.35   | 3.09 3.09  | 2.25 2.25   | 2.16 2.16   |
| 2 <sup>1</sup> / <sub>2</sub> 6x6x <sup>3</sup> / <sub>4</sub> " | 16.88 13.88   | 16.88 13.88   | 16.88 13.88  | 16.88 13.88   | 16.88 13.88   |
| 1 <sup>1</sup> / <sub>2</sub> 13x1"                              | 13.00 11.00   | 13.00 11.00   | 13.00 11.00  | 13.00 11.00   | 13.00 11.00   |
| 1 <sup>1</sup> / <sub>2</sub> 13x1"                              |   |   |  |   | 13.00 11.00   |
|  | 32.97 27.97   | 35.23 30.23   | 33.97 27.97  | 32.13 27.13   | 45.04 38.04   |
| Flange Sect.   |  |  |  |  |  |

From Specifications thickness of web  
to be not less than  $\frac{1}{60}$  of unsupported  
dist. between flange  $L_s = \frac{3.54 \times 12}{60} = .265"$   
 $\therefore$  3/8" R as used satisfies the specifications










ROLLER BEARING AT  
ABUTMENT & BASCULE PIER



DETAIL OF HINGE








# Concrete Deck

Sheet A-7

Span 4'-9"  
Dead load 100#/ft.  
Paving 40#/ft.  
140



$$3.33 \times 3.33 = 11.11'$$

$$\frac{10000}{11.11} = 900 \text{ #/ft.}$$

$$900 + 140 = 1040$$

$$M = 1040(4.5)(4.5)1.5 = 31590 \text{ "#} + 30\% I = 41067 \text{ "#}$$

$$d = \sqrt{\frac{41067}{12 \cdot 113}} = 5" + T = 7"$$

$$A_s \text{ at Center} = \frac{41067}{16000 \cdot 7 \cdot 6} = .48"$$

Stringers Span 13'

$$M_c = 5000 \cdot 6.5 = 32500 \text{ ft. #}$$

$$M_u = \frac{715 \cdot 13 \cdot 13}{8} = 15100 \text{ " "}$$


$$47600 \text{ " "}$$

$$47600 \times 12 = 571200 \text{ in. #}$$

$$\text{Shear} = 6.5 \times 715 = 4650 \text{ #}$$

$$5000 \text{ #}$$

$$9650 \text{ #}$$



$$\text{Sect. Mod.} = \frac{571200}{16000} = 35.6$$

Use 12" C.I. @ 31.8 #

## FLOOR BEAMS


L.L. Rear wheels 6'-0" apart, 10000# on ea. wheel  
Uniform load = 80 x 4.75 = 380# per ft. of stringer

$$\text{Reaction} = 380 \times 6.5 = 2470 \text{ #}$$

$$R_1 = 10000 + \frac{5000 \times 3.33}{13.33}$$


$$= 10000 + 1245 = 11245$$

$$R_1 = 11245 + 2470 = 13715 \text{ #}$$





$$R_3 = 13715 + 13715 + 7000 \\ = 34430 \#$$



Moments

$$M_c = 34430(10.75) - 7000(9.5) - 13715(4.75) = 248977 \#'$$

$$M_b = 34430(6) - 7000(4.75) = 173330 \#'$$

$$M_a = 34430(1.25) = 43038 \#'$$

L.L. Shears

$$R_3 \text{ to } a = 34430 \#$$

$$a \text{ to } b = 27430 \#$$

$$b \text{ to } c = 13715 \#$$

DEAD LOADS

Paving 140 #/b'

$$140 \times 4.75 \times 13.33 = 8864$$

$$I.B.m. 31.8 \times 13.33 = 424$$

$$F.R. 100 \times 13.33 = 1333$$

$$\underline{10621}$$

$$D.L. \text{ Girder } 4.75 \times 800 = 3800$$


$$\underline{14421}$$

$$R_3 = 36300$$

$$M_c = 36300(10.75) - 7300(9.5) - 14500(4.75) = 252000$$

$$M_b = 36300(6) - 7300(4.75) = 183125$$

$$M_a = 36300(1.25) = 45375$$



# Summary of Stresses FLOOR BMS.

Sheet - 9

|                          | a                       | b                       | c                       | R3                      |
|--------------------------|-------------------------|-------------------------|-------------------------|-------------------------|
| DL Shears                | 36300                   | 29000                   | 14500                   | 36300                   |
| L.L. "                   | 34430                   | 27430                   | 13715                   | 34430                   |
| I "                      | 10329                   | 8229                    | 4115                    | 10329                   |
| Total                    | 81059                   | 64659                   | 32330                   | 81059                   |
| Section Regd.            | 8.106 Gr.               | 6.466 Gr.               | 3.233 Gr.               | 8.106 Gr.               |
| Web used                 | 32x $\frac{3}{8}$ = 12" | 32x $\frac{3}{8}$ = 12" | 32x $\frac{3}{8}$ = 12" | 32x $\frac{3}{8}$ = 12" |
| Moments ft. #            |                         |                         |                         |                         |
| D.L. Mom.                | 45375                   | 183125                  | 252000                  | 0                       |
| L.L. "                   | 43038                   | 173330                  | 248477                  | 0                       |
| I "                      | 12911                   | 51999                   | 74543                   | 0                       |
| Total                    | 101324                  | 408454                  | 575020                  | 0                       |
| Eff. Depth               | 2.38'                   | 2.38'                   | 2.38'                   |                         |
| Flange Stress            | 42600                   | 172000                  | 242000                  |                         |
|                          | Gr. Net                 | Gr. Net                 | Gr. Net                 | Gr. Net                 |
| Flange Regd              | 3.66                    | 2.66                    | 11.76                   | 10.76                   |
| Sect. Used               | 16.12                   | 15.12                   |                         |                         |
| '8 Web                   | 1.50                    | 1.50                    | 1.50                    | 1.50                    |
| 2LS 6x6x $\frac{3}{4}$ " | 16.88                   | 13.88                   | 16.88                   | 13.88                   |
|                          | 22.04                   | 18.04                   | 30.14                   | 26.14                   |
|                          | 34.50                   | 30.50                   |                         |                         |

End Stiffeners  $\frac{81059}{12000} = 6.76"$  2LS 4x4x $\frac{9}{16}$

Intermediate Stiffeners 3 $\frac{1}{2}$ x3 $\frac{1}{2}$ x $\frac{3}{8}$  LS Spaced @ 2'4"

Used fillers under all stiffeners

Use 7 rivets

$\frac{81059}{12000} = 6.75$  Use 10 rivets in end stiffeners

Use 7 rivets in intermediate stiffeners

See Detail drawing AD-1 for more complete details

## DESIGN OF HINGE

R for Dead Load = 106600  
 R " Live " = 42700  
 R " Impact = 12800  
 162100

Design of hinge Ctd.

Assume pin Dia. = 7"

$$\text{Bearing area} = \frac{162110}{20000} = 8.1"$$

$$8/7 = 1\frac{1}{7}" \text{ say } 1\frac{1}{2}"$$

$$\left. \begin{array}{l} \text{Web} = \frac{3}{8}" \\ 2\text{Rs} @ \frac{5}{8}" = 1\frac{1}{4}" \\ \text{Total} = 1\frac{5}{8}" \end{array} \right\} \text{ on Cantilever End.}$$

2 Pin Rs @  $\frac{3}{4}" = 1\frac{1}{2}"$  on suspended End.

$$\text{End Stiffeners } \frac{162110}{12000} = 13\frac{1}{2}" \text{ Use } 2\text{Ls } 5 \times 5 \times \frac{3}{4}"$$

See detail drawing AD-1

$$n = \frac{162110}{7880} = 20.6 \text{ say 21 rivets}$$

$$\frac{33}{21} = 2 \text{ lines of rivets @ } 3" \text{ o.c.}$$

DESIGN OF END ROLLERS

Abutment end.

Bascule pier end similar

|            |   |        |
|------------|---|--------|
| D.L. react | = | 109400 |
| L.L. "     | = | 56500  |
| Impact "   | = | 16950  |
|            |   | 182850 |

Allowable pressure on Concrete =  $400 \frac{\text{lb}}{\text{in}^2}$ 

$$\text{Bearing R req'd. on abutment} = \frac{182850}{400} = 456.9"$$

Use Bearing R  $21\frac{1}{2} \times 21\frac{1}{2} \times 2"$ 

Space rollers 1" apart

$$\text{Bearing on rollers } 600D = 600 \times 3 = 1800 \frac{\text{lb}}{\text{lin. inch}}$$

Starting rollers at  $\frac{3}{4}"$  from ea. end

$$21\frac{1}{2}" - 1\frac{1}{2}" = 20", 6 \text{ rollers Spaced @ } 4" \text{ c-c.}$$

Cast Steel Pedestal

$$\text{length of rollers } 19", 6 \times 19 = 114", 114 \times 1800 = 205000$$

PIN

Pin length = 16"; assuming dia. of 4"



$$S = \frac{182850}{4 \times 16} = 2857 \text{ \#/' OK}$$

Compression area of pedestal not less than  
 $\frac{182850}{16000} = 11.42"$  Detail on Drwg. AD-1

R3

D.L. Reaction = 322600#

L.L. " = 56500 #

$$I = 96780^{\#}$$

474880

Bearing  $\Delta$  req'd on abutment  $\frac{474880}{400} = 1188^\circ$   
 " " " =  $34\frac{1}{2} \times 34\frac{1}{2} \times 2$

3 Rollers  $600 \times 3 = 1800$  # per inch of bearing

$$\frac{474800}{1800.30} = 8+$$

Use 9 rollers 3" Dia.


Space rollers  $\frac{1}{2}$ " apart

$9 \times 3 + 8(1.5) = 31''$  Start rollers  $1\frac{3}{4}''$  from ends

Pin assume 6" dia.

Compression area of pedestal not less than

Compression area of pedestal not less than

$$\frac{474800}{16000} = 29.68 \text{ in}^2$$


Reg'd. area for pins

$$s = \frac{474800}{6 \times 24} = 3292 \text{ #/o} \quad \text{O.K.}$$

Design of web splices  
Suspended girder  
2 splices will be req'd.

20 feet from R1 & 20 feet from hinge

Design of web splices Ctd.  
20' from R1

|                                 |   |                      |             |                |
|---------------------------------|---|----------------------|-------------|----------------|
| Moments, D.L.                   | = | Fl. # 1,513,500      | Shears D.L. | 61400          |
| " L.L.                          | = | 421500               | " L.L.      | 9400           |
| " I                             | = | 126450               | " I         | 2920           |
| " Total                         |   | <u>2066450 Fl. #</u> | " Total     | <u>73620 #</u> |
| Actual net flange area = 38.11" |   |                      |             |                |

$$\text{Mom. taken by web} = \frac{3.23}{38.11} \times 2066450 = 175500 \text{ Fl. #}$$

$$\text{Stress in splice Pls} = \frac{175500 \times 12}{42} = 50000 \text{ #}$$

The max. allowed unit stress on the extreme fibre of the girder = 16000 #/sq in

Max. allowable unit stress on the splice plates

$$= \frac{21}{32} \times 16000 = 10500 \text{ #/sq in}$$

$$\frac{50000}{10500} = 4.76 \text{ " Req'd. 2 Pls } 6 \times \frac{3}{4} \text{ "}$$

$$\text{net area} = 9 \text{ "} - 2 \times 2 \times 1 \times \frac{3}{4} \text{ "} = 6.00 \text{ "}$$

Allowable rivet stress

$$= \frac{21}{32} \times 12000 = 7800 \text{ #}$$

$$\text{Number of rivets on each side of splice} = \frac{50000}{7800} = 6.5 \text{ (not less)}$$

Number of rivets req'd. in vertical splice

$$\frac{73620}{7800} = 9.45 \text{ on ea. side (not less)}$$


Shear Pl

$$\frac{73620}{10000} = 7.36 \text{ "}$$

$$\text{Thickness} = \frac{7.3}{2.36} = .11 \text{ "}$$

3/4" Pl used. to act also as filler

$$\text{Rivets} = \frac{73620}{12000} = 6.13$$



Length of cover plates

From Johnson Bryan &amp; Turneaure Modern Framed Structures Part III

$$x_n = L \left( \frac{a_1 + a_2 + \dots + a_n}{A} \right)^{\frac{1}{2}}$$

Length of outer cover PL,  $x_1 = L \left( \frac{a_1}{A} \right)^{\frac{1}{2}} = 60 \left( \frac{11}{45.03} \right)^{\frac{1}{2}} = 29.64'$ 

Adding 8" to ea. end for 2 extra lines of rivets the adopted length becomes 31'-0"

Length of 2<sup>nd</sup> cover PL

$$x_2 = L \left\{ \frac{a_1 + a_2}{A} \right\}^{\frac{1}{2}} = 60 \left\{ \frac{11 + 11}{45.03} \right\}^{\frac{1}{2}} = 41.70'$$

Adding approx. 8" to ea. end for 2 extra lines of rivets the adopted Length becomes 43'-0"

Stiffeners at abutments & bascule piersTotal reaction 148530, of this it will be assumed that, due to the deflection of the girder, 60% or  $0.60 \times 148530 = 89118$ Assuming permissible bearing stress at 24000 #/in.<sup>2</sup> reqd. bearing area of 2 Ls on the flange Ls =

$$\frac{89118}{24000} = 3.71'' \text{ assuming L with } 5'' \text{ net bearing length} = 4\frac{3}{8}''$$

Reqd. thickness of each stiffener =  $\frac{3.71}{2 \times 4.38} = .423''$  or  $\frac{7}{16}''$  with 3" net to web the Ls will be  $5 \times 3 \times \frac{7}{16}$ 

Use same size Ls for outer stiffeners. Use fillers

Radius of gyration of 2 Ls separated by  $1\frac{3}{8}''$  about an axis in the plane of the web =

$$r = \left\{ \frac{2(2.19(3.44)^2 + 1.12(1.128)^2)}{6.62} \right\}^{\frac{1}{2}} = 2.88$$

Eff. length of stiffener = 40"

allowable stress =  $p = 19000 - 100 \times \frac{40}{2.88} = 17600 \text{ #/in.}^2$ 

$$\frac{89118}{17600} = 5.08'' \text{ Reqd. area furnished} = 6.62 \text{ O.K.}$$

Stiffener rivetsSince loose fillers are used, the number of rivets will be increased 1% for each  $\frac{1}{16}''$  of thickness of fillers or 24% Safe resistance of one  $\frac{7}{8}''$  rivet in bearing on  $\frac{3}{8}''$  web =

$$\frac{7}{8} \times 0.375 \times 24000 = 7880 \text{ #}$$



Number of rivets

$$\frac{89118}{7880} = 11.33 \text{ not less \& exclusive of those in Flg. Ls.}$$

Intermediate Stiffeners

Space as shown on drwg. AD-1

Outstanding legs to be about  $\frac{1}{30}$  depth of girder  
 $+ 2" - \frac{48}{30} + 2 =$  Use  $3\frac{1}{2} \times 3 \times 8$  Ls. with fillersFlange RivetingSpacing is computed at center of each panel  
 Since the angle of slope for the lower chord is small, it will not be taken into account

$$\text{For the lower chord } p = \frac{u d}{K V}$$

$$\text{For the upper chord } p = \frac{u}{\left\{ \left( \frac{K V}{d} \right)^2 + w^2 \right\}^{\frac{1}{2}}}$$

u = least value or safe resistance of rivet.

V = Total shear at cross section.

w = Vertical load per inch of length applied directly to flange

d = Effective depth of girder

K = A flange stress apportionment factor, representing the ratio of the total stress borne by a part or all, of the flange material proper to the total stress borne by the full flange area, including the web equivalent

Pitch at Support

Least value of V of a 7" rivet on 8" web =

$$28 \times \frac{3}{8} \times 24000 = 7880 \#$$

Eff. Depth approx. 60"

$$K \text{ for the tension flange} = \frac{\text{Area of } 2 - 6 \times 6 \times \frac{3}{4} \text{ Ls. less } 4 \text{ } 1\frac{1}{4} \text{ holes}}{13.88 \div 13.88 + 8 \text{ web}} = \frac{13.88}{17.11} = .81$$

$$K \text{ for Comp. flange (based on gross area)} = \frac{16.88}{20.11} = 0.84$$

$$V = 140000 \#$$

$$w = \frac{7000}{12} = 584 \#/\text{lin. inch} \quad p = \frac{7880 \times 60}{140000 \times 0.81} = 4.18" \quad \text{Spacing } 4"$$

For Top flange

$$p = \frac{7880}{\sqrt{\left( \frac{.84 \times 140000}{60} \right)^2 + 584^2}} = 3.60" \quad \text{Spacing } 3\frac{1}{2}"$$

Flange riveting Ltd.

At 20 feet from end.

$$V = 106600$$

$$K \text{ for bott. flange} = \frac{35.88}{38.31} = 0.94$$

$$K \text{ " top " } = \frac{42.88}{45.31} = 0.95$$

$$p \text{ for bott. fl.} = \frac{7880 \times 60}{106,600 \times 0.94} = 4.7" \text{ Use } 4\frac{1}{2}" \text{ Spacing}$$

$$p \text{ for top " } = \frac{7880}{106,600 \times 0.95} = 6\frac{1}{2}" \text{ Use } 6" \text{ Spacing}$$

$$\sqrt{\left(\frac{.95 \times 106600}{60}\right)^2 + 584^2}$$

At center of span use 6" spacing for both top &amp; bott. chords.

Cover Plate RivetingRivets in pairs opposite to each other.  $p = \frac{2vd}{KV}$ 

$$U = 7220 \text{ for } \frac{7}{8}" \text{ rivet}$$

$$d = 57"$$

$$K \text{ for Bott. Flange} = \frac{11}{28.11} = .392$$

$$K \text{ for Top flange} = \frac{13}{33.11} = .392$$

$$V = 140000\#$$

$$p \text{ for bott. flange plate} = \frac{2 \times 7220 \times 57}{.392 \times 140000} = 15"$$

Use 6" spacing throughout except for 18 inches at each end where a spacing of  $3\frac{1}{2}"$  will be adopted.

For further details see drawing AD-1

Intermediate Girder


Splices will be made at points f, h & j.  
 at h shear will be zero, since it is the center of the span, therefore, splice will be designed to resist bending only

Moment of resistance of web =  $\frac{1}{8} A_w f_c d$

$$= \frac{1}{8} \times 41 \times \frac{3}{4} \times 16000 \times 41 = 1,265,000 \text{ in.}^2$$

Use 2 vertical splice plates 12" x  $\frac{3}{4}$ " and 2 horiz. plates 5 $\frac{1}{4}$ " wide on the flange angles.

Since safe stress on flange rivets @ 20.5" from neutral axis = 7880, safe stress on one rivet at 1 inch from neutral axis =  $\frac{7880}{20.5} = 385$



Moment of resistance in vertical splice plates on one side of splice when "y" = vertical distance of any rivet from neutral axis.

$$= 385 [4(1.5^2 + 4.5^2 + 7.5^2 + 10.5^2 + 13.5^2)]$$

$$= 385 [4(2.25 + 20.25 + 56.25 + 110.25 + 182.25)] = 650,000$$

Difference in moment of resistance now developed by horizontal splice plates =  $1,265,000 - 650,000 = 615,000$

$$2n \times 7880 \times 41 = 615,000$$

$$n = \frac{615,000}{2 \times 7880 \times 41} = 1.955$$

Use 4 rivets each side of splice spaced at 5 in.

The flange rivets must transfer the horizontal increment of flange stress from web to flanges in addition to developing the moment of resistance of web splice.

The average horizontal rivet spacing over splice in top flange taking  $K = 0.95 =$

$$p = \frac{7880}{\sqrt{\left(\frac{0.95 \times 5}{41}\right)^2 + 584^2}} = 13.4$$

Number of rivets req'd. to transmit Hor. increment of flange stress =  $\frac{7.5}{13.4} = 1.56$

$\therefore 1.955 + 1.56 = 3.515$  rivets since never less than 2 rivets should ever be used 3 will be adopted for each side of splice



The horizontal splice plates must transmit the stress carried by .95 rivets =  $.95 \times 7880 = 7480$   
 Net area of 2 Pls. =  $7480 \div 16000 = .468''$  or  
 $.468 \div 2 = .234''$  for each plate. Use  $5\frac{1}{2} \times \frac{1}{2}''$  Pls.  
 $5.25 \times .25 = 1.31''$  each, which is satisfactory.

Splices at f & j will be made the same as each other Moment. Since the D.L. mom. is the greater (see Table of stresses on Sheet 46), the splice will be designed using the full D.L. Mom. =  $1,291,000 \text{ ft}\cdot\text{lb}$   
 Shear =  $225820 \text{ lb}$

Actual net effective flange area =  $27.97''$   
 Bending mom. carried by web =  $\frac{3.09}{27.97} \cdot 1,291,000 = 143,000$   
 Assume hor. splice Pls.  $12 \times \frac{3}{4}''$   
 Stress in hor. " " =  $\frac{143000 \times 12}{42} = 40800 \text{ lb}$   
 Max. allowable stress on extreme fibre of girder =  $16000$   
 " " " " Hor. Splice Pls =  
 $\frac{21}{35} \times 16000 = 9600 \text{ lb/in}^2$

Req'd. area splice plates =  $\frac{40800}{9600} = 4.26''$   
 or 2 Pls.  $12 \times \frac{3}{4}''$  But  $\frac{3}{4}''$  Pls have been adopted because of thickness of flange Ls. & to stiffen the splice.

Since the fibre stress was reduced on splice plates so the rivet stress will be reduced in proportion to their distance from the neutral axis.  $\frac{21}{35} \times 7880 = 4720$   
 Number of rivets on each side of splice =  $\frac{40800}{4720} = 8.65$   
 " " " " " " vertical splice Pls.  
 req'd. to resist shear =  $\frac{225820}{7880} = 28.6$  Use 30 each side


Flange Riveting  
 Both chord  $P = \frac{Vd}{KV}$

Top chord  $P = \frac{V}{\left\{ \left( \frac{KV}{d} \right)^2 + w^2 \right\}^{\frac{1}{2}}}$

pitch at support

$U = 7880$  for 8 rivets on  $\frac{3}{8}''$  web  
 $d = 108''$

K for the tension flange = Area of 2-6x6x $\frac{3}{4}''$  Ls



$$\begin{aligned} \text{less } 4 \times \frac{15}{16} \text{ holes} &= 13.880'' \\ 1 \times 13 \times 1 \text{ less 2 holes} &= 11.000'' \\ \hline &= 24.880'' \end{aligned}$$

$$K = \frac{24.88}{24.88 + 5.35} = .823 \text{ for tension flange}$$

$$K \text{ for comp. flange} = \frac{29.88}{29.88 + 5.35} = .84$$

$$V = 244450$$

$$w = 584 \#/\text{inch}$$

$$\text{Tension flange } p = \frac{7880 \times 108}{.823 \times 244450} = 4.12''$$

$$\text{Comp. flange } p = \frac{7880}{\sqrt{\left(\frac{.84 \times 244450}{108}\right)^2 + 584^2}} = 3.96''$$

Spacing at Pier Both flange 4' o.c. top flange 3 1/2' o.c.  
Point f

$$K = \frac{24.88}{24.88 + 3.09} = .894 \text{ for tension flange}$$

$$K = \frac{29.88}{29.88 + 3.09} = .910 \text{ for comp. flange}$$

$$p = \frac{7880 \times 63}{.894 \times 225820} = 2.46 \text{ for tension flange}$$

$$p = \frac{7880}{\sqrt{\left(\frac{.91 \times 225820}{63}\right)^2 + 584^2}} = 2.38 \text{ for comp. flange}$$

Space rivets in 2 rows stagger at 2 1/4' o.c.  
both top & bott. flange

Point f & j

K = same as at Supt. for both tension & comp. flanges

$$V = 175400$$

$$w = 584 \#/\text{inch}$$

$$\text{Tension Flange } p = \frac{7880 \times 63}{.823 \times 225820} = 2.68''$$

$$\text{Comp. Flange } p = \frac{7880}{\sqrt{\left(\frac{.84 \times 225820}{63}\right)^2 + 584^2}} = 2.62''$$

Space @ 3' o.c. in both tension & comp. flanges.  
in two rows staggered

Point g & i

$$K = \frac{24.88}{24.88 + 2.25} = .918 \text{ for Tension flange}$$

$$K = \frac{29.88}{29.88 + 2.25} = .930 \text{ " comp. "}$$

$$p = \frac{7880 \times 45}{.918 \times 175400} = 2.19" \text{ for tension flange}$$

$$p = \frac{7880}{\sqrt{\left(\frac{.930 \times 175400}{45}\right)^2 + 584^2}} = 2.49" \text{ for comp. flange}$$

Space rivets @ 4" o.c. staggered 2 rows to center.

### Riveting of cover plates

$$p = \frac{2vd}{KV}$$

At point e

$$d = 63"$$

$$v = 7880 \text{ for } 7/8" \text{ rivet}$$

$$K = \frac{11}{11 + 13.88 + 3.09} = .394 \text{ for tension flange}$$

$$K = \frac{13}{13 + 16.88 + 3.09} = .395 \text{ for comp. flange}$$

$$V = 153400$$

$$p = \frac{2 \times 7880 \times 63}{.394 \times 153400} = 16.5" \text{ Actual pitch in line of stress must not exceed 6" Therefore pitch in both top & bott. flanges will be 6"}$$

At Support

$$d = 100" \quad V = 244450$$

$$K = \frac{11}{11 + 13.88 + 5.35} = .363 \text{ for tension flange}$$

$$K = \frac{13}{13 + 16.88 + 5.35} = .368 \text{ for comp. flange}$$

$$p = \frac{2 \times 7880 \times 100}{.363 \times 244450} = 17.70"$$

A spacing of 6" will be adopted for both top and bott. flanges for full length of girder

### Stiffeners

At Supports.

Reaction = 429450# of this (due to the deflection of girder) 60% will be assumed to be carried by each pair of Ls.

$$429450 \times .6 = 257670$$

Assuming permissible bearing stress = 24000 #/sq in.  
the reqd. bearing area of 2 Ls =  $\frac{257670}{24000} = 10.73 \text{ sq in.}$

2 Ls  $3\frac{1}{2}" \times 5" \times \frac{3}{4}"$  with  $3\frac{1}{2}"$  leg next to web

Radius of gyration about an axis in the plane



of the web =  $r = 3.00$

Effective length = 50"


The permissible compressive stress =  $19000 \cdot 100 \frac{50}{3}$   
 $= 17335 \text{ #/sq in.}$  limiting the stress to  $13000 \text{ #/sq in.}$

Req'd. area of 2 Ls =

$$\frac{257670}{13000} = 19.70"$$

Therefore instead of a single pair of Ls it will be necessary to provide two pairs as shown in sketch. Also use solid  $\frac{3}{4}$ " filler plate under entire group of stiffeners and floor beam.

Intermediate Stiffeners  
 Make same as those  
 used in suspended  
 girder.



Note. in both top and  
 bott. chords the 1st. cover  
 plate will be carried  
 full length of girder both flngs.

2nd. cover plate will  
 be extended from  
 points "e" to "e" over  
 both piers in top flange &  
 from flt. in bott. flange



Note. Due to the rigidity of the reinforced  
 concrete deck, and also the gusset plates  
 extending from bottom chords of floor beam  
 to bottom chords of main girders it was  
 assumed that any further bracing to resist  
 wind or sway would be superfluous.

When encasing main girders unusual care  
 must be exercised to keep any grout from  
 entering hinged joint. This may be avoided by  
 inserting asphaltic board between the two face  
 angles of the joint, removing same after conc.  
 has set.

# Design of Piers

Sheet #21

Fin Rdway

Weight of conc. 150#/cu. ft.

Reaction at each Pedestal = 429450# Total 1 9/16"

" " " " D.L. = 356000#

Surface of approach exposed to wind = 8 square ft per lin ft.

Velocity of current at surface = 5 miles per hour

Ice & drift collected about the upstream end of the pier for a depth of 6' below high water level & for an average width of 18 feet.

Wind pressure 30#/ft

Overturning moments

Wind pressure

$$80 \times 8 \times 30 = 19200 \#$$

Acting at a distance of 22.25' above base of pier

Overturning moment = L.W. Line

$$19200 \times 22.25 \times 12 = 5,126,400 \text{ in} \#$$

Pres. on pier =  $3 \times 5 \times 30 = 450 \#$

$$\text{Mom.} = 450 \times 13.5 \times 12 = 7290 \text{ in} \#$$

Overturning pres. due to current

$$2.96 \times 5^2 = 74 \#/\text{ft} \text{ at surface}$$

$$\text{at bott} = \frac{74}{2} = 37 \#/\text{ft} \text{ at bott of drift}$$

$$6 \times 18 \times \left( \frac{74 + 37}{2} \right) = 5994 \#$$

If  $p$  represents the intensity of pressure at the surface, &  $p_i$  the intensity of pressure at the bottom of the ice, and  $d$ , the distance from the surface to the bottom of the ice, the distance  $x_0$  from the surface to the center of pressure =

$$x_0 = \frac{(2p_i + p)d_i}{3(p_i + p)}, p = 74, p_i = 37, d_i = 6'$$

$$x_0 = \frac{[2(37) + 74]6}{3(37 + 74)} = \frac{888}{333} = 2.66' \text{ \& } 8.34' \text{ to bott.}$$

$$\text{Overturning mom.} = 5994 \times 8.34 = 50000 \text{ ft.} \#$$

$$\text{Pressure of water on pier below ice} = 5 \times 5.5 \times 19 = 523 \#$$

$$\text{Mom.} = 15696 \text{ in.} \#$$



Length of pier at cap = 30'-0"

at base = 32'-0"

Design of piers Ctd.  
Summary of overturning moments


Sheet #A22

|                                 |               |
|---------------------------------|---------------|
| Wind Pressure on bridge         | 5,126,400 in# |
| " " pier                        | 7290 "        |
| Due to current on ice & drift   | 600,000 "     |
| Due to water pressure below ice | 15,696 "      |
| Total overturning Moment        | 5,749,386 "   |


Resisting Moment

Taking moments about the downstream lower edge of ftg.


Wt. of ftg. =  $31 \times 6 \times 150 = 27900$  #  
Mom. =  $27900 \times 17 = 474,300$  #ft



Stem.  
Wt. = 248,550  
Mom. =  $248,550 \times 17 = 4,225,350$  #ft



Coping Wt. = 15,750  
Mom.  $15,750 \times 17 = 267,750$  #ft



It is obvious that, even without taking into consideration the effect of the reaction from the bridge, the pier is safe from overturning, therefore no further calculations will be necessary. (Reinforce both faces with  $\frac{1}{2}$ " bars 12" o.c. both ways)  
Pier will rest on rock

Abutments

|                       |               |
|-----------------------|---------------|
| Reactions From Bridge | D.L. 109,400  |
|                       | L.L. 30,100   |
|                       | I. 9,030      |
|                       | Total 148,530 |

See sheet #A23 for sketch  
The back wall from bridge seat to finished Roadway will be designed as a cantilever retaining wall  
Hgt. of wall = 11'-6"  
Width at top 10"  
" " base 1'-4"

L.L.  
Load on each rear wheel = 10,000 #. This will be assumed as acting over an area of  $10 \times 3$   
L.L. per ft =  $\frac{10,000}{30} = 333$  # + 30% impact = 432 #/ft  
L = 18,000,  $f_c = 700$



Scale of Forces  $1'' = 100,000^{\#}$   
Scale of Dist.  $\frac{1}{4}'' = 1'-0''$

Equating this Live Load to an equivalent surcharge  
taking earth at 100#/cu. ft.  $\frac{432}{100} = 4.32'$  equivalent filling

$p = 0.2948wh$  at bott.

$= 0.2948 \times 100 \times 16.33 = 482 \text{ #/ft.}$

at top

$p = 0.2948 \times 100 \times 4.32 = 127 \text{ #/ft.}$

$H = 1470 \cdot 100 \cdot \frac{16.33^2}{2} = 3950 \text{ #}$

$M = 0.5896wh^3$   
 $= 0.5896 \cdot 100 \cdot \frac{16.33^3}{3}$   
 $= 257000 \text{ in #}$

$bd = \frac{M}{R}$

$d = \sqrt{\frac{257000}{12 \cdot 113}} = 13.72'$   
Bridge Seat


Allowing 3" for  
steel protection  
thickness of  
wall at bott. = 17"

$A_s \text{ at bott. } = \frac{257000}{18000 \cdot \frac{2}{3} \cdot 14} = 2.2''$

$7\phi @ 6\frac{1}{2}"$  Stop one half of bars at  $\frac{1}{3}$  of wall hgt.

Mom. at  $\frac{2}{3}$  hgt. from bott. =  $0.5896 \cdot 100 \cdot \frac{8.12^3}{3} = 31400 \text{ in. #}$

$A_s = \frac{31400}{18000 \cdot \frac{2}{3} \cdot 9} = 2.21''$



The abutment will be designed as a counterfort type reinforced concrete abutment.

Counterforts Spaced at 8'-0" o.c.

The base plate will be assumed to be 24" thick  
Pressure sustained by lower foot of slab -  $P = \frac{1}{3}Wh$

$$P = \frac{1}{3} \times 100 \times 31 = 1033 \text{ #/ft.}$$

$1033 \times 8 = 8264 \text{ #}$  Total load per strip one ft. wide between counterforts

$$M = \frac{8264 \times 8 \times 12}{8} = 99168 \text{ in #}$$

$$bd^2 = \frac{M}{K} \quad d = \sqrt{\frac{99168}{12 \times 113}} = 8.55$$

Allowing 3" for protection of reinforcing  $8.55 + 3 = 11.55$   
The wall will be made 12" thick throughout.

$A_s \text{ at bott.} = \frac{99168}{18000 \times \frac{8}{9} \times 9} = .70 \text{ #}$  Use 3# @ 10' o.c. Bend alternate bars. Use this steel & spacing for 3 ft. up from bott.

$$P = \frac{1}{3} \times 100 \times 28 = 934 \text{ #}, W = 934 \times 8 = 7472$$

$$M = \frac{7472 \times 8 \times 12}{8} = 89600 \text{ in #}$$

$$A_s = \frac{89600}{18000 \times \frac{8}{9} \times 9} = .634 \text{ #} \quad 3\# @ 11' \text{ o.c.}$$

$$P = \frac{1}{3} \times 100 \times 24 = 800 \text{ #}, W = 800 \times 8 = 6400 \text{ #}$$

$$M = \frac{6400 \times 8 \times 12}{8} = 76800 \text{ in #}$$

$$A_s = \frac{76800}{18000 \times \frac{8}{9} \times 9} = .54 \text{ #} \quad 3\# @ 10' \text{ o.c.}$$

$$P = \frac{1}{3} \times 100 \times 20 = 666 \text{ #} \quad W = 666 \times 8 = 5328 \text{ #}$$

$$M = \frac{5328 \times 8 \times 12}{8} = 63800 \text{ in #}$$

$$A_s = \frac{63800}{18000 \times \frac{8}{9} \times 9} = .45 \text{ #}, 5\# @ 8' \text{ o.c. to top. Bend alt. bars.}$$

For temperature bars,  $\frac{1}{2}\# @ 12' \text{ o.c.}$  will be used at right L's to main reinforcing.

$$H = 0.1474wh^2 = 0.1474 \times 100 \times 31^2 = 14150$$

$$14150 \times 8 = 113,200 \text{ # Total pressure on counterfort}$$

This will act at  $\frac{1}{3} \times 26.5 = 8.82 \text{ ft.}$  from bottom.

$$\text{Mom. in counterfort} = 113200 \times 8.82 \times 12 = 12,000,000 \text{ in #}$$

The counterforts will be made 16" wide

Depth at top of flg. = 11.3 feet

" " Bridge seat = 2.5 "

The counterfort can be designed as a T beam since the vertical slab forms at with the counterfort.





Design of Abutments Ctd.

Sheet #A27

Location of resultant of vertical loads

$$(67360 \times 4.75 + 40800 \times 8.5 + 15600 \times 4.75 + 12700 \times 6.75 + 450 \times 7.36 + 5400 \times 6.41 + 10500 \times 10.75 + 21600 \times 6.41 + 185000 \times 12.29) \div 359410 = 3,386,000 \div 359410 = 9.45'$$

The resultant falls within the middle third therefore the abutment is safe against overturning.

$$\text{Pressure at toe} = (4 \times 17 - 6 \times 6.75) \frac{359410}{17^2} = 27.5 \left( \frac{359410}{17^2} \right)$$

$$= 34200$$

$$\frac{34200}{8} = 4260 \#/\text{ft. of toe}$$

$$\text{Pressure at heel} (6 \times 6.75 - 2 \times 17) \frac{359410}{17^2} = 6.5 \left( \frac{359410}{17^2} \right)$$

$$= 8060, \quad 8060 \div 8 = 1000 \#/\text{ft. of heel.}$$

Design of toe

$$\text{Av. pres.} = \frac{4260 + 3400}{2} = 3830 \#$$

$$\text{Mom.} = \frac{3830 \times 4.25^2 \times 12}{2} = 415000 \text{ in}\#$$

$$d = \sqrt{\frac{415000}{12 \times 113}} = 17.5"$$

The Ftg. was assumed to be 24" thick. All ftgs. should have a min. of 4" protection for reinforcing steel  $\therefore 17.5 + 4 = 21.5$  say 22"

$$U = \frac{4.25 \times 3830}{12 \times \frac{7}{8} \times 10} = 86.2 \text{ which is rather high for}$$

Concrete without spec. provision for diagonal tension  
Using a depth of Ftg. of 24" total depth

$$U = \frac{4.25 \times 3830}{12 \times \frac{7}{8} \times 20} = 77.6 \text{ a } 45^\circ \text{ fillet will be}$$

provided as shown on sketch Sheet #A23  
this makes the shear at edge of fillet =

$$U = \frac{3.25 \times 3830}{12 \times \frac{7}{8} \times 20} = 59\% \text{ and by inspection it can}$$

be seen that the shear will be less at face of wall.

$$A_s = \frac{415000}{18000 \times \frac{7}{8} \times 20} = 1.31 \text{ in}^2 \quad 3\# @ 5\frac{1}{2}" \text{ o.c.}$$

longitudinal shrinkage reinforcement  $\frac{1}{2}\# @ 12" \text{ o.c.}$

Design of rear portion of Ftg.

Since the weight of the rear portion will not act unless the wall is about to overturn & since the

Design of Abutments Ctd.

Sheet #A28

the calculations show that the abutment is stable against overturning, only the weight of the earth with its superimposed Live Load plus impact will be considered in designing the rear portion of flg.

$$2.3 \times 11.25 \times 100 = 2700$$

$$9.42 \times 29.00 \times 100 = 27300$$

$$30000\#$$

The flg. will be a beam continuous over the counterforts.

$$M = \frac{30000 \cdot 8^2 \cdot 12}{12} = 1,920,000 \text{ in}\#$$

$$d = \sqrt{\frac{1,920,000}{11.75 \times 12 \times 113}} = 11"$$

$$U = \frac{30000 \times 4}{141 \cdot \frac{7}{8} \cdot 7} = 86\% \text{ which is excessive without stirrups}$$

For the sake of rigidity the flg. will be given an effective depth of 20", then becomes

$$\frac{30000 \times 4}{141 \times \frac{7}{8} \times 20} = 48.4\% \text{ Stirrups will be unnecessary}$$

$$A_s = \frac{1,920,000}{18000 \times \frac{7}{8} \times 20} = 6.08" \quad 8-1\#, 4Bt. \& 4St.$$

There will be a tendency for the wall slab to tear away from the counterforts, this stress will vary with the depth & will be pure tension since the counterforts must be provided with reinforcing to resist shrinkage stresses, stirrups will be used extending from back of counterforts thru & into the wall.

$$\text{Tension at bott. of wall} = 8264\#, \quad \frac{8264}{18000} = .458"$$

$$2 \text{ legs of } \frac{1}{2}" \text{ stirrups} = .38"$$

Place  $\frac{1}{2}" \square$  @ 10" o.c. for  $\frac{1}{3}$  of hgt. of counterfort

$$\text{At } \frac{1}{3} \text{ hgt. Tension} = 5328\#, \quad \frac{5328}{18000} = .296"$$

Place  $\frac{1}{2}" \square$  @ 16" o.c. to bridge seat

There will also be a force tending to tear the counterfort away from the rear portion of footing



## Design of Abutments Ctd


Sheet # 429

Weight of earth =  $30000 \times 8 = 240000 \text{ lb}$

$$\frac{240000}{18000} = 13.3 \text{ ft} \quad 2 \times 8 \text{ ft legs} = 16 \text{ ft}$$

$$\frac{13.3}{1.60} = 22 \quad \text{Use } 22 \times 8 \text{ ft } \angle \text{ embed } 8 \text{ ft into counterfort}$$

## Design of Bridge seat



### PLAN OF ABUTMENT

Total D.L. = L.L. I =  $141820 \text{ lb}$  Concentrated on wall

This load will be distributed by means of the bridge seat. To accomplish this  $4 \times 3 \times 8 \text{ ft}$  bars will be placed under bridge seats.

Area of pedestal =  $2.835 \times 2.835 = 8.04 \text{ ft}^2$

$$\frac{141820}{8.04} = 17650 \text{ lb/ft}^2$$

Taking an effective area of  $9 \times 12 = 108 \text{ ft}^2$ , then  $\frac{17650}{108} = 163 \text{ lb/ft}^2$ . Which is a very low unit comp. stress.

The wings are designed in the same manner as the abutment.

Foundation is assumed to be rock, & will be scored to provide resistance to sliding.

Back filling against abutment is not to be placed until after all dead load of bridge is in place.